

TRANSVERTER MISCELLANEOUS TESTS  
CROSSBAR TANDEM OFFICES  
ARRANGED FOR CAMA

1. GENERAL

- 1.001 This addendum supplements section 220-501-503.
- 1.002 It is reissued to change test steps required when the transverter is arranged to handle ODMU (Optional Detail Billing) traffic.

4. METHOD

The following changes apply to Part 4 of the section:

- (a) Test I, steps 11m, 32m, 91m, 92m, and 93 - added.

STEP	ACTION	VERIFICATION
I. Registration Error		
11m	If office is arranged for ODMU - Block operated NDB relay	
Over Registration		
32m	If office is arranged for ODMU - Operate DET relay momentarily	XRE relay operated, released
Under Registration		
91m	If office is arranged for ODMU - remove blocking tool from NDB	XRE relay operated
92m	Block operated NDB relay	XRE relay released
93	Remove all blocking tools	

TABLES

The following changes apply to Table B:

Table B

CONNECT SPRING	GROUND TO RELAY	PUNCH OR LAMP
10T	DTB-1	DTB *
6T	NDB	NDB *

\* If transverter is equipped to provide the record