

# MEASUREMENTS AND DATA MANAGEMENT NETWORK ADMINISTRATION "DMS\* "-10 DIGITAL SWITCHING SYSTEM

	CONTENTS	PAGE	CONTENTS P	PAGE
١.	GENERAL	2	8. DATA SUMMARIZATION	13
2.	NETWORK DATA RESPONSIBILITIES—NON-MECHANIZED	2	A. Nonmechanized	13
3.	NETWORK DATA RESPONSIBILITIES—MECH-		8. DATA SUMMARIZATION	13 13
	ANIZED	3	A. Nonmechanized	13
4.	DATA COLLECTION—MECHANIZED AND NONMECHANIZED	4	C. DMS-10 Switching System NSPMP Re-	13
	A. Communications Link	4	quirements	15
	B. Operational Measurements System		9. DATA ANALYSIS	15
5.	(OPMS)	5	10. REFERENCES	16
Э.	DATA MESSAGE OUTPUT—MECHANIZED .	7	Figures	
	A. General Description	7	Sample A Schedule, DMS-10 Switching System EDAS Feature Output	28
	B. A Schedule (30-Minute Message) .	9	2. Sample D Schedule, DMS-10 Switching Sys-	
	C. Data—Demand Basis	10	tem EDAS/TSMS Feature Output	29
6.	BUSY HOUR DETERMINATION	10	3. Operational Measurements Block Printout Format	30
	A. General Description	10	4. Operational Measurement Data Flow—	
	B. Nonmechanized TCBH Determination	10	Mechanized and/or Nonmechanized .	31
	C. A Schedule TCBH Determination	11	5. Example of TTY Session to Query Control Data Items for Measurement Blocks	32
7.	TRAFFIC SEPARATIONS	12	6. Recent Change Order—Operational Measurement Control	33
	A. Nonmechanized (OPM Format)	12	7. Example of TTY Session to Change Control	
	B. Mechanized (D Schedule Format) .	13	Data Items of Measurement Blocks	34
* R	egistered Trademark of Northern Telecom Ltd.		8. Recent Change Order—Study Register .	35

# NOTICE

This document contains proprietary information that cannot be released outside Bell Communications Research (Bellcore) except to a regional Bell company without written permission of Bellcore.

	CONTENTS	PAGE
9.	Example of TTY Session to Add a Study Register	
10.	Recent Change Order—Operational Measurements Hunt Group	
11.	Example of a TTY Session to Activate a Hunt Group	
12.	DMS-10 Switching System Data Output Formats	
13.	Data Summarization Form	43
14.	COER Output	61
15.	Data Reliability Comparison Worksheet .	82
Tables		
A.	Operational Measurements	17
В.	DMS-10 Switching System Measurement Blocks	
C.	Control Data Items Prompts and Responses	
D.	Index—Data Summarization Forms	
U.	maex—bala summarization roffis	23
E.	COER ODF Contents Requirements	26

# 1. GENERAL

- 1.01 This section describes the data management task of the network switching administrator (NSA) for the Digital Multiplex System-10 (DMS-10) switching system. This section includes information related to all current generics. Responsibility, data collection, report scheduling, data analysis, and data summarization and distribution are topics that are discussed.
- 1.02 This section is reissued to include the information for the 208, 209, and other generic programs, and the variations between the mechanized and nonmechanized data modes. Since this is a gen-

eral revision, no arrows have been used to denote significant changes.

- 1.03 The title for each figure includes a number(s) in parentheses which identifies the paragraph(s) in which the figure is referenced.
- 1.04 For a detailed description of the measurements available in the DMS-10 switching system, refer to Northern Telecom Practice (NTP) 297-3001-456, Operational Measurements.

# NETWORK DATA RESPONSIBILITIES—NONMECHA-NIZED

- 2.01 The NSAs are responsible for manually scheduling, collecting, validating, posting, and distributing data required to properly administer, evaluate, and engineer the DMS-10 switching system when the system is defined (via the generic conditions [GCON]) as nonmechanized. When the mechanized feature is purchased, defined in GCON as EDAS, and activated the structure of the measurements, scheduling, collection, etc, is drastically altered. These differences will be discussed in detail in later paragraphs.
- 2.02 In the nonmechanized mode, the NSA must identify and obtain the data required for the following:
  - (a) Network Administration
  - (b) Traffic Engineering
  - (c) Trunk Servicing and Forecasting
  - (d) Traffic Separations
  - (e) Business Services
  - (f) Special studies for interdepartmental coordinates
  - (g) Network Switching Performance Measurement Plan (NSPMP)
  - (h) Other reports as required by local and company practices.
- 2.03 The nonmechanized data are collected by data block content, referred to as Operational Measurements (OPM), and the proper distribution is de-

termined based on local and company practices. Prior to distribution, the raw data must be validated and then tested for reliability. Validation and reliability procedures generally consist of initial comparisons of the current data to a "historically" developed set of standards determined for each office. The standards are derived by comparison of initial data to those engineering standards that were applied to the provisioning of a switching entity. These derived historical standards are then applied to machine data outputs on an ongoing basis.

- applied data reliability and validation technique may result in a coordinated effort with maintenance groups. This effort is necessary to resolve situations where data may not reflect actual equipment operation, or may reflect a defective data collection or storage device. The responsibility for data validation belongs to the NSA, although mutual interdepartmental responsibilities are shared. It is also the responsibility of the NSA to provide the valid data in a mutually acceptable format which is usable by the receiving department.
- 2.05 Data analysis is just one part of a total switching system analysis that incorporates a review of the measured load, service, and volume of traffic. The office and component, engineered and administrative capacities should be determined followed with a routine monitoring of load versus capacity. Inherent in this analysis is an evaluation of the future service capability of the office. Specific future service areas to be monitored are:
  - (a) Switching system capacities of lines, terminals, switching paths, and common control components required to evaluate the actual system performance.
  - (b) Data analysis and reliability checks on key items of office data and tests of actual or projected values. This is with continued evaluations of actual capacities and office characteristics to determine any change in the current office exhaust dates.
  - (c) Assessments of office growth and utilization versus the load and growth forecasted on the demand and facility (D&F) charts.

# 3. NETWORK DATA RESPONSIBILITIES—MECHANIZED

Effective with generic 209.10 and later a purchased feature (EDAS) is available for data collection into a mechanized system (eg, Engineering and Administration Data Acquisition System [EADAS]). (See Note.) When the EDAS feature is provided, it is defined to the DMS-10 switching system via the System Parameters (SYS) Configuration Record. In addition an input/output (I/O) port must be defined for data transmission from the EDAS feature to the data collection system under the Logical Unit (LOGU) section of the Configuration Record. With the definition of both the feature (EDAS) and the port (LOGU), the data is sent on a unidirectional interface whereby only output messages are sent from the DMS-10 switching system to the data collection system (eg, EADAS). This unidirectional interface precludes putting EADAS in the DMS-10 switching systems at this time.

**Note:** Throughout this practice, two terms are utilized. They are:

- EDAS—This is the nomenclature used by Northern Telecom to designate the feature formatting area in the I/O area for passing data to a data processing system. Whenever the term EDAS is used, it denotes the internal view as seen by the DMS-10 switching system in its processing of data for downstream processing.
- EADAS—A data processing system used in many area of the Bell Operating Companies.
- 3.02 The messages sent on the I/O port to the data collection system are limited to three. The three messages are:
  - (a) The 30-minute message (also called the A schedule)
  - (b) The 24-hour message (also called the D schedule)
  - (c) SYSLOAD messages.
- 3.03 An example of the A schedule output is shown in Fig. 1, and an example of the D schedule output is shown in Fig. 2.

- graph 2.01, under a mechanized environment are somewhat reduced. The scheduling task has been eliminated when the EDAS feature is defined in the DMS-10 switching system. The DMS-10 switching system will accumulate the data over a 30-minute interval for some measurements, and over a 1-hour interval for other measurements. The data is transferred to the holding registers from the accumulators then sent to the EDAS formatting section. These fixed accumulation intervals of 30-minute data are transferred out of the DMS-10 switching system at each hour and half-hour over the entire 24 period. The D-schedule data is transferred out of the DMS-10 switching system every hour on the hour each day.
- 3.04 The data collecting function has been eliminated by the fixed internal times of A and D schedules.
- 3.05 Some areas of validation are eliminated by the introduction of a set of validity (VAL) measurements in each of the two measurement schedules. These measurements are only in place to allow the data user to judge the reliability of the data. Further elementary validation is provided in downstream processing (eg, Central Office Equipment Reports [COER]). However, the final judgment of data validation still remains the responsibility of the NSA.
- 3.06 Distribution of mechanized data is further reduced if, eg, COER is used. This system will distribute the trunking data, and provide the NSA and engineers with summarized reports based on the extreme value (EV) concept. Historically, downstream processed data has been summarized by utilizing the time-consistent busy hour(s) for the office and its components. The EV concept application will report the peak data points for each reported day, and a time-stamp to indicate the hour in which the peak occurred.
- 3.07 The information contained in paragraphs 2.03, 2.04, and 2.05 is applicable to data responsibilities in the mechanized as well as the nonmechanized mode. Information contained in later paragraphs and figures illustrate and explain the differences in the mechanized and nonmechanized modes.

# 4. DATA COLLECTION—MECHANIZED AND NON-MECHANIZED

# A. Communications Link

- 4.01 The NSA's communication link with the DMS-10 switching system is the traffic TTY. The traffic TTY is one of a maximum of eight terminals that the DMS-10 switching system can support. This terminal can operate at 110, 300, 1200, 2400, or 4800 baud rates depending on the type of terminal chosen. A detailed description of all TTY ports and the input/output (I/O) system can be found in NTP 297-3001-300 or Section 241-120-030.
- In the DMS-10 switching system, a number of programs are stored on tape rather than being kept resident. Upon request, these are loaded into resident memory, one at a time. There are two types of overlay programs: (1) interactive and (2) freerunning. Interactive programs are structured in dialogue form and require an interchange of information between the program and the program user. The OPM output is typical of an interactive mode of overlay program. The free-running programs require no dialogue between the user and the programs. A typical free-running program is the maintenance program that surveys system integrity. The traffic TTY, in conjunction with the Operational Measurement Control (OMC) system, is the medium through which measurement reports are received.
- The DMS-10 switching system has space in its 4.03 resident memory for only one overlay program to be run at a time. Requests to run an overlay program can come from a terminal or from within the system. The system may request a program as a result of detecting a fault or because a scheduled program is due to be run. When a manual request is forwarded to the I/O system while the overlay area is in use, DMS-10 switching system sends a message to the requesting terminal indicating which program is being run and the user of that program. The receiver of the message can then elect to override the program in the overlay area by issuing an appropriate command. The user of the aborted program is notified that the program has been aborted.
- 4.04 The routing of output messages to specific terminals is controlled through the use of message classes. Typical output message classes are data modification, maintenance, and traffic. The maintenance class of terminal has priority on overlay areas.

Assignment of message classes can be found in NTP 297-3001-304 under the Logical Units (LOGU) Configuration Record 05.

- 4.05 Passwords are required to gain access to the DMS-10 switching system from a terminal. Attempts to access the system through the use of an unauthorized password will result in the user being blocked. Passwords are also used to control the classes of tasks that may be performed by users of the I/O system, ie, a password class of "Traffic" is allowed traffic measurement tasks. Passwords are assigned in translations under the Passwords (PSWD) Configuration Record.
- 4.06 To permit user verification of information entered through a terminal keyboard, the I/O system echoes all input characters with the exception of the password. The I/O system operates in either the input or output mode to prevent garbling. In the input mode, the system echoes input characters to the terminal for verification and stores output messages in a buffer for later output. In the output mode, the system ignores all inputs (except the octothorpe [#] and asterisk [\*] which form part of two abort commands) and outputs any messages it may have accumulated in the output buffer. A user can enter the output mode from the input mode by depressing the carriage return key at the end of a line. Carriage return is indicated by <CR> in all examples of terminal sessions. Also, the system changes to the output mode when more than 60 seconds has elapsed since the last character had been input. A user can enter the input mode from the output mode by entering the abort command ####. Basic system prompts and typical user responses may be found in Section 241-120-030.
- Special commands are used to abort an over-4.07 lay program and to abort the current command. The abort commands can be used with the I/O system operating in either the input or output modes. If an overlay program is in use, the program can be aborted by typing four consecutive asterisks within a 10-second period. After the program is aborted, the I/O system enters the input mode in anticipation of further instructions. Another overlay program can be loaded by the system or by another user once the current overlay is aborted. A request to abort the current command is accomplished by inputting four consecutive octothorpe characters within 10 seconds. This causes the program to abort the command and enter the input mode in anticipation of further input.

If no overlay program is loaded in the overlay area, the use of either command causes the I/O system to enter the input mode.

4.08 If an error is made while inputting data from a terminal, the DMS-10 switching system will respond with an error message. Consult the Output Message Manual for interpretation of the message.

# B. Operational Measurements System (OPMS)

- 4.09 The DMS-10 switching system has programs resident in system memory which monitor system performance and level of service. The programs accumulate data associated with various system functions. The data is stored and transmitted based on the responses to the GCON definitions as stated in paragraph 2.01. Data is transferred to holding registers and configured in a set of measurement blocks called OPMS. A full description of the OPMS can be found in NTP 297-3001-456. See Table A for the types of OPMS data collected by the DMS-10 switching system.
- The DMS-10 switching system uses a doublebuffer arrangement for measurements. As OPMS data are collected, it is stored in accumulating registers. The contents of the accumulating registers are transferred to the holding registers at regular intervals according to an update schedule, if the system is in the nonmechanized node, or every 30 minutes if the system is in the mechanized mode. In transferring, the contents of the accumulating registers are either added to or copied over the contents of the holding registers, or placed in the holding registers after the previous contacts that were transferred to the EDAS formatting area were cleared, dependant on the GCON option responses. The update schedule and option are specified by using the OPMS control program when the DMS-10 switching system is nonmechanized. The update schedule and option are disabled when the EDAS feature is part of the system, and it is activated.
- 4.11 Stored OPMS data may be lost because of a system reload. A system reload can be invoked either automatically by the system as a recovery action from severe system faults or manually as a trouble clearing procedure. This causes all OPMS registers to be set to zero. Hence, all OPMS data collected since the last printout is lost. A system reload is indicated by printout SYS000 (on the traffic TTY) or in the VAL section of the EDAS output format

(the third register will contain a figure other than 00000).

4.12 The contents of the holding registers are printed out or sent to the EDAS formatter, at specified intervals according to the GCON option response. On specification, the value in the holding register is either set to zero or left intact, depending on the GCON option. The data are printed out on a particular class of TTY, according to a defined print class. The printout schedule, option, and print class are specified by using the OPMS control program or the GCON option response.

**Note:** In the nonmechanized mode, if a holding register overflows, ie, value exceeds 65,536, the value printed out for the register is \*\*\*\*\*. The five asterisks indicate a value in excess of 65,536 for a particular OPMS data item. However, in the mechanized (ie, EDAS/Traffic Separations Measurement System [TSMS]) mode, the valid range is from 0 through 65525. The integers 65526 to 65536 are reserved as special codes for the special codes in a data collection system (eg, EADAS).

- 4.13 The OPMS data may also be printed out on demand. The user (eg, the traffic TTY) may obtain a printout of the data accumulated in the holding registers of all (or selected) measurement blocks since the last scheduled printout or data transferred to the EDAS formatter in the I/O system. On printing by request, the value in the holding registers is left intact.
- 4.14 The OPMS data are printed out as scheduled in the nonmechanized mode or on demand at the traffic TTY in the mechanized mode in the form of measurement blocks. Figure 3 shows the printout format for the first OPMS data block, and Fig. 4 shows the dataflow. The format is similar for all measurement blocks in the mechanized or nonmechanized mode.
- 4.15 Table B displays all of the measurement blocks that are currently available in the OPMS if the blocks were to be examined on a demand basis, either in the mechanized or nonmechanized mode. It shows all of the counts (mnemonics) that appear in each block and the registers that are printed for each one when the nonmechanized or mechanized mode of data collection is used. This table is designed for use as a quick reference. A de-

tailed description of each count can be found in NTP 297-3001-456. The primary source for user interface using a TTY or cathode-ray tube (CRT) display may be found in NTP 297-3001-300, DMS-10 switching system output/output system and NTP 297-3001-456 (Addendum).

- 4.16 The major difference between the mechanized and nonmechanized data is the point at which the data is examined. As stated, the accumulators and holding registers contain data in OPMS format. In the mechanized mode, the data is transferred from holding registers into the I/O area where the data is arranged into a message format which is sent in ASCII encoded characters at the baud rate (generally 1200 baud) specified for the EDAS data link. The release of generic 209 included several "new" accumulators. However, some of these accumulators cannot be examined in the DMS-10 switching system.
- 4.17 The following is an example of data transfer and the effect it may have on data analysis from the point of view of the NSA. For example:
  - (a) At 10:00 am, the data accumulated between 9:30 am and 10:00 am is transferred to the holding registers. Any data residing in the holding registers is zeroed.
  - (b) As the data is placed in the holding registers it is also transferred to the I/O area for formatting via the EDAS interface.
  - (c) With 209 generic and later, the added accumulators do not have corresponding holding registers. The data is transferred directly to the I/O area and the data is sent on the channel marked for EDAS output.
  - (d) When downstream data reports (eg, exception reports from EADAS), are examined and the NSA wishes to examine the corresponding data in the DMS-10 switching system, those accumulators which do not have corresponding holding registers cannot be examined. Other methods will have to be employed to analyze the data (see Part 9. Data Analysis).
- 4.18 The DMS-10 switching system provides for user control of the OPMS. Various collect and printout options are available in the nonmechanized mode through a control block associated with each OPMS block. The options or control data items are

specified for a complete measurement block, not for individual measurements within a block. The control data items are:

- (a) Update schedule
- (b) Update option
- (c) Printout schedule
- (d) Printout option
- (e) TTY class for printout.

The options or control data items associated with mechanized data mode are explained in and shown in Table C.

- 4.19 User control of the OPMS is provided by the Operational Measurements Control (OMC) program. The program is an overlay program (ie, held on magnetic tape) and is explicitly loaded into system memory by the user when required. The mechanism for inputting data via the program is interactive. The system prompts the user for the type of information to enter on the TTY. Of the following tasks listed, all are fully applicable to the DMS-10 switching system in the nonmechanized mode. Tasks (a) and (b) are partially applicable to the mechanized mode, and (c) and (d) are fully applicable. Overlay program OMC is used to perform the following tasks:
  - (a) **Query** control data items for measurement blocks (see Fig. 5)
  - (b) **Change** control data items for measurement blocks (see Fig. 7)
  - (c) Manipulate traffic study registers (see Fig. 9)
  - (d) *Manipulate* the OPMS for the purpose of obtaining measurements on hunt groups (see Fig. 11).

Figures 6, 8, and 10 are Recent Change Orders designed to be used as work sheets to prepare specific Data Modification Orders or TTY prompt-response sessions accessing the OMC overlay.

4.20 Office data are stored in system memory and on tape. The data are automatically entered into system memory following each Data Modifica-

tion Order (DMO) when the carriage return is depressed. Making a change using the overlay OMC is considered DMO. The DMO overlay programs use two commands to control the storing of data on tape. (The tape is the back-up for the DMS-10 switching system.) These commands are TAPE (TP) and NO TAPE (NOTP). The TP command transfers data from system memory onto tape immediately following each DMO operation. To enter this mode, the user inputs the TP command in response to the first prompt following the loading of each overlay program. The user need not input the TP command. The NOTP command inhibits transfer of office data from system memory onto tape. The data are entered into system memory only. This is the default mode which exists when any DMO overlay program is loaded. The user need not input the NOTP command. This is the recommended mode where several DMO operations are being performed during one session in order to avoid excess time being taken up by tape operations.

- 4.21 Refer to Table C for the prompts and options available for changing the control data items using overlay OMC. Table C also includes an indicator to those prompts-responses that are not applicable to the mechanized option.
- 4.22 If the NOTP command is used, whether by input or default, the data must be transferred from the system memory onto the tape when all DMO operations are finished. The data are transferred by using the Equipment Data Dump (EDD) program. The user loads overlay program EDD into system memory and enters DUMP <CR> in response to the first prompt.

# 5. DATA MESSAGE OUTPUT—MECHANIZED

# A. General Description

5.01 The introduction of an interface between the DMS-10 switching system and a data collection system, eg, EADAS, resulted in a "formatting" of the OPM data blocks into a different grouping of the data register message. Additional measurements were added in the accumulator area. Unlike the measurements in the OPM data blocks, some of the new measurements do not have corresponding holding registers, and the "new measurement" data is transferred to the I/O formatting area directly from the accumulators.

- The DMS-10 switching system measurement data is formatted into American Standard Code for Information Interexchange (ASCII) encoded characters via the TTY I/O port from a Serial Data Interface (SDI) circuit, then across a data link defined in the GCON area of the DMS-10 switching system. As stated in paragraph 4.10, the update schedule and most options are disabled when the EDAS feature is activated (see Table C). The measurements are transferred according to an interval time table. The measurements are provided over a fixed interval of 30 minutes. At the conclusion of the fixed 30-minute periods, the values in the accumulators are transferred to the holding registers. The holding registers are zeroed (as in the case of the A schedule message) or added (on the half-hour as in the case of the D schedule message) as the current value data is inserted. Each half-hour interval the A-schedule data from the holding registers, along with the data which does not have holding registers, is transferred and placed in the format area of the I/O for transmission to the data collection system.
- 5.03 The data accumulation of the A schedule measurements starts on each hour and half-hour and is transferred to the holding registers and I/O 30 minutes later. The data accumulation for the D schedule measurements begin on the hour and are transferred from the holding registers and I/O 1 hour later. On each hour when both the A schedule message and the D schedule message results are transferred, the A schedule message is always sent out on the data link first, followed immediately by the D schedule message. Figure 4 shows a diagram of the data flow in the DMS-10 switching system with the EDAS feature applied and activated.
- 5.04 In addition to the OPM data provided by the DMS-10 switching system in a nonmechanized mode, several accumulators have been added to provide additional measurement capabilities. They are:
  - (a) Validity measurements
  - (b) Maintenance usage on a trunk group basis
  - (c) Maintenance usage on multifrequency (MF) and DGT (DIGITONE\* signaling) receivers
  - (d) Maintenance usage on network and junctor loops

- (e) Real-time usage measurement of the processor.
- 5.05 Mechanized DMS-10 switching system measurements are grouped into records, sections, and messages. When the EDAS feature is activated, the I/O format area arranges the OPM data into these groupings.
- 5.06 When there is a set of measurements relating to one item, such as a trunk group, they are defined as a record. Each record begins with a numeric code that identifies the items contained in the rest of the measurements in the record. For example, an outgoing trunk group would be arranged as follows:
- (1) (2) (3) (4) (5) 00019 00123 01234 00001 00036
- (1) = identifier of the trunk group number
- (2) = peg count on the trunk group (includes any peg counts in (4) over-flow) during the period
- (3) = usage on the trunk group (including any usage appearing in (5) maintenance busy) during the period
- (4) = peg count of the attempts to access a circuit in the group and all sensors were busy due to traffic maintenance outage
- (5) = usage on those trunks that are placed in a maintenance status either due to faulty circuit, manually made-busy, or machine-made busy. This usage would not include a maintenance call from an incoming test desk trunk.
- 5.07 The EDAS format area compiles related individual measurements and records then groups them into sections. The individual measurements are in specific locations within a section and the record measurements are shown by their group identifier.

<sup>\*</sup> Registered service mark of Northern Telcom Ltd.

The defined sections and their measurement types (individual or record) are:

- (a) Validity (VAL = individual measurements)
- (b) Office Totals (OFT = individual measurements)
- (c) Features (FEA = individual measurements)
- (d) Processor (PRO = individual measurements)
- (e) Component (CMP = individual measurements)
- (f) Service Network (SNW = record measurements)
- (g) Conference Circuit (CON = record measurements)
- (h) Network Circuit (PCK = record measurements)
- (i) Junctor (JTR = record measurements)
- (j) Customer Group (CGM = record measurements)
- (k) Customer Line (CLM = record measurements)
- (l) Outgoing Trunk Group (TKO = record measurements)
- (m) Incoming Trunk Group (TKI = record measurements)
- (n) Traffic Separations (DOR = record measurements)
- (o) Auxiliary A (AXA = individual measurements) (see Note)
- (p) Auxiliary B (AXB = individual measurements) (see Note)

**Note:** Only appears if the DMS-10 switching system is arranged as a Centralized Automatic Message Accounting (CAMA) office.

5.08 The length of time required for messages transmission to the data collection system (eg, EADAS) depends on three variables, the data trans-

mission speed, the size of the message, and any intramessage pauses. The transmission of all messages scheduled to be sent to the data collection system during a given half hour, must be completed prior to the start of the next half-hour.

5.09 The speed of data transmission is variable as stated in paragraph 4.01. The interface provides one-way outgoing communications from the DMS-10 switching system to the data system. Any pauses in the data transmission caused by any messages (eg, maintenance and alarm messages) merely delay the remainder of the message transmission. These messages are allowed by the system.

# B. A Schedule (30-Minute Message)

- from the DMS-10 switching system will consist of all of the sections listed in paragraph 5.07, except the DOR section. The message content is organized into data lines of variable lengths. The lines are grouped into the sections, with some sections of a fixed number of data registers, and other sections of variable number of data registers. Each register is a fixed width of five numeric characters. The content of each register will consist of leading zeros, if the register field is not full, and will be right justified.
- 5.11 Each A schedule message contains a header line. This line consists of:
  - (a) The message type = MSG A
  - (b) The entity identifier (14 characters)
  - (c) The ending time of the 30 minute collection interval = hour: minute (for example, 09:30). The hour will be expressed as 00 to 23.
  - (d) The last field will consist of the month, day, and year (for example, 03/20/83).
- 5.12 The sections that make up the A schedule are identified by one of the three character identification (IDs) listed in paragraph 5.07. The last character of the ID is separated by two spaces prior to the beginning of the first register contents. It should be noted that the VAL section is always the first section to appear on the A schedule output to the data collection system. The OFT section is second, followed by the FEA, etc, until the AXA or AXB is completed.

Upon completion of the last line of the message, the A schedule will print END in the left of the message column vertically aligned under the section ID.

5.13 Each section of the A schedule, following the section ID, uses the first data register to indicate the quantity of individual registers to appear in the section. The initial register in a section that contains record measurements gives the number of measurement registers for each record. For example, the VAL section contains a 00005 in its first entry to indicate the presence of 5 individual measurements in the section in addition to the initial register. Also the CON section contains a 00005 in its first entry to indicate there are always 5 registers in the conference circuit record. An explanation of each section of the A schedule and the content of the individual section are shown in Fig. 12.

#### C. Data—Demand Basis

- 5.14 Data may be requested from a user at any time. The printout/display will contain data stored in the holding registers of all or those measurement blocks desired. The output will contain the data contained at the time of the last scheduled update of the holding registers. Whenever data is requested, the contents of the holding registers are not zeroed. Data will be printed/displayed in the OPM format shown in Fig. 1.
- switching system holding registers is output in the OPM format, and raw data from a request of the data collection system (eg, EADAS) will be as defined in the sectionalized format of paragraph 5.07. Examination of the two output formats will require a correlation for analysis. Figure 12 contains this correlation of OPM data block relationship and the entries within the sections of the EDAS format output.

# 6. BUSY HOUR DETERMINATION

#### A. General Description

6.01 Approximately 2 weeks after an office cutover, at a prescribed interval, a busy hour study should be completed. This 2-week interval is to allow the various factors that cause a new office to vary its data reporting to reach a relatively stable condition. Section 780-200-031 discusses general theories and procedures to be used for end office busy hour determination. Regardless of the data collection mode, mechanized or nonmechanized, the busy hour determination study should be exercised.

- In addition to the data collection method. another factor for busy hour determination should be considered. It must be determined if the busy hours data are in the average busy season busy hour (ABSBH) or extreme value (EV) format. Data from the DMS-10 switching system will be in either the OPM or EDAS output format. The NT 8611, Equipment Questionnaire and Traffic Worksheets, are oriented into analog and digital shelves for circuit packs, load (expressed in hundred call second [CCS]) on analog and digital shelves, receivers and transmitters, and processor. These pages and calculations should be used for capacity statements in Section 241-120-060. The major impact of busy hour determination on the NSA work group will be based on selection of the data format and collection. Calculations and selection of the time consistent busy hour (TCBH) are still required for the office busy hour (OBH), and service busy hours (SBH) for the DMS-10 switching system NSPMP (see Section 241-140-005). This may be performed regardless of the collection made. Only the methodology will be slightly different.
- 6.03 Logically, the nonmechanized (OPM format) lends itself to manual data examination and use of the TCBH for all aspects of data reporting. The mechanized (EDAS format) will pass data through a data collection system (eg, EADAS) and the output will be in either an EV format (peak time frames only reprinted) or TCBH dependant on the methods used by the data collection system. If a data summarization system (eg, COER) is utilized the reports, monthly and machine load and service summary (MLSS), will consist of EVs.

### B. Nonmechanized TCBH Determination

- 6.04 It is advisable to utilize half-hourly data for busy hour determination in the nonmechanized mode. However, hourly data may be used if there is a definite busy hour after the first 5 days of the study, but the start-stop times of the study period should not be limited to the "on-the-hour" time frame.
- 6.05 The office busy hour should be established using half-hour data (or hourly, if local procedures state) carrying the highest usage (CCS load) on the MUX loops. Using the output of OPM 006, total

OFFICE

the USE (usage) registers of the SNWK, CONF, and the PESH registers. These usage registers contain:

- (a) PESH—The usage on all time slots on the MUX loops between the peripheral shelves and the network shelves.
- (2) CONF—The usage on all time slots on the MUX loops controlling the access to the conference circuits. Locations on the common equipment (CE) bays are preset and assigned as required.
- (3) SNWK—The usage of all time slots on the MUX loop controlling access to the tone sources and digital senders on the service network.

**Note:** These "dedicated" MUX loops are not available for talking path calls.

The Data Summarization Form in Fig. 13 (Sheet 13) may be utilized for data entry comparison of hour in half-hourly data.

- 6.06 The JCTR (junctor) measurements are not included as part of the busy hour determination requirements on the MUX loops as this information is contained in the PESH measurements. The JCTR data consists of that load for timeslot pairs which carriers information between the networks.
- the same manner as the office busy hour, except the data block utilized is DPM 005. The USE entries on the data block for DIGITONE (DGT) signaling and multifrequency (MF) receiver should be examined to determine the busy hour for the components. The Data Summarization Forms in Fig. 13 (Sheets 7 and 8) may be utilized for the data entries comparison of hourly on half-hourly data.
- 6.08 Component busy hour ratios should be established for DIGITONE signaling and MF receivers if the busy hour is different from the office busy hour established in paragraph 6.06. For example, a DIGITONE signaling receiver busy hour is determined at 10:00 am with an average CCS of 150. During the office busy hour of 16:00 (4 pm), if

DIGITONE signaling receivers averaged 100 CCS, the ratio would be:

150 CCS ÷ 100 CCS = 1.5 Component (Office Busy Hour) Busy Hour Ratio.

"DIGITONE"

	BUSY HOUR	BUSY HOUR
Time	10:00	16:00
Avg CCS	150	100
Component Busy Hour Ratio	(1.5)	(1.0)

These calculated component busy hours should be reported to the network switching engineer (NSE) for future use in office addition engineering.

- 6.09 It is normally not practical to print the data blocks 24 hours a day for manual operation. In order to print the data blocks for selected hours, the print (PRNT) option should be set to the desired days of the week (DOWK). When DOWK is utilized, start (STRT) and stop (STOP) are required. The response for STRT is a number from 0 to 23. In this case, printing access hourly on the hour specified. The response for STOP must be equal to or greater than STRT. The DMS-10 switching system provides no option that allows reports to start and stop more than once within the same 24-hour period.
- **6.10** Additionally, a TCBH CCS/line should be calculated. This may be accomplished by the following formula:

6.11 Service busy hours in the nonmechanized mode should be calculated for dial tone delay and matching loss per instructions given in Section 241-120-050.

# C. A Schedule TCBH Determination

6.12 The usage registers in sections SNW (service network), CON (conference circuits), and PCK

(peripheral shelves) are the formatted equivalent of the PESH, CONF, and SNWK in OPM 006. Figure 1 illustrates a representative printout of the A schedule from the EDAS formatter of the DMS-10 switching system. Figure 12 makes a side-by-side comparison of the OPM data blocks and the formatted A schedule.

- 6.13 The current mechanized data collection (EADAS) does not contain a method of performing a BHD study, and the busy hour selection should be manually calculated until a summarization module is developed. The CCS content of the usage registers will need to be manually extracted and added to obtain the total office load.
- 6.14 Examination of Fig. 12, the SNW, CON, and PCK section will explain which registers to extract. As an example, the SNW section may be explained as:
  - (1) The first register always contains a 00005. It indicates that each SNW record in the section contains five registers.
  - (2) Registers 00001 to 00005 in both the A schedule format and the OPM format are given common numbers for easier interpopulation.
  - (3) The contents of register 00004, 00009, etc, are the usage registers for the 1st, 2nd, etc, service network MUX loops.

The same register pattern is followed in the CON and PCK sections of the A schedule output. The Data Summarization Form in Fig. 13 (Sheet 13) may also be utilized for data entry to total the register contents.

device with the EDAS feature will be output every half-hour with no control over the number of hours. If a data collection system (eg, EADAS) is used that does not contain a data summarization module, the system will require interrogation at various intervals to print the A schedule contents. An alternative to interrogation would be the use of exception reporting (eg, NORGEN) with the thresholds for the usage registers set to a low level in order to collect the required usage data to determine to TCBH for the office.

- 6.16 Service circuit BHD may be done in a manner similar to that just described for the office busy hour, except the CMP (component) section of the A schedule output would be utilized. Figure 12 also compares the CMP registers to the content of OPM 005. The same register numbering utilized is utilized. For example:
  - (1) The first CMP register indicates that 46 (00046) registers are contained in the section.
  - (2) Registers 3 and 8 in OPM 005 and registers 00003 and 00008 in CMP are usage registers for DIGITONE signaling receivers and MF receivers, respectively.
- 6.17 Data Summarization forms in Fig. 13 (Sheets 7 and 8) may also be used for data entry of half-hourly data to determine the TCBH for the various components. As stated in paragraph 6.16, the use of exception reporting techniques (eg, NORGEN) may also be utilized as an additional aid to determine the component TCBH.
- 6.18 If a significant difference is noticed between the OBH and the component BH, the ratios stated in paragraph 6.09 should be calculated. These results should be retained and the NSE should be notified.
- **6.19** The TCBH CCS/line may be accomplished by the following formula:

Total PCK CCS + Total CON CCS + Total SNW CCS

= CCS/Line

## Total Customer Lines

6.20 Service busy hour using register readings from the OFT section of the A schedule should be calculated for dial tone delay and matching loss using instructions given in Section 241-120-050.

## 7. TRAFFIC SEPARATIONS

# A. Nonmechanized (OPM Format)

7.01 Traffic Separations utilizing the OPM data block format can use Fig. 13, Sheet 18, for recording one week of the total monthly peg count. All 24 hours do not have to be posted as long as the "ADD" option is used on the holding registers. For example, if the data blocks are scheduled to print to the terminal starting at 8:00 am and stopping at 10:00

pm, it will be necessary to manually add only the hourly registrations from 8:00 am to 10:00 pm. In addition, the first readings of each day must be added to this subtotal. This 8:00 am reading will provide all of the counts from 10:00 pm of the previous day until 8:00 am of the current day. The end result is a total 24-hour count from 10:00 pm to 10:00 pm. A full minutes-of-use study for Traffic Separations will require that OPM blocks 001, 002, 003, 004, and 005 be collected 24 hours a day, 7 days a week and forwarded to the Traffic Separations group for summarization.

# B. Mechanized (D Schedule Format)

7.02 The Traffic Separations measurements are provided by the DMS-10 switching system with the Traffic Separation Measurements System (TSMS) feature, and reported to the data collection system via the EDAS feature. The contents of the D schedule consist of two sections, the VAL and DOR. The VAL section contains the same data as the VAL section of the A schedule, except the content of the last two registers will contain a higher peg count due to the longer collection internal.

7.03 The D-schedule information is transferred from the accumulators to the holding registers at the end of every 30-minute period. Unlike the A schedule, the D schedule data is held and two 30-minute periods are added together, then transferred to the I/O formatting area on the hour. The summarized data is passed to the terminal used by the data collection system.

7.04 Data from the D schedule is available on a demand basis from other terminals. Unlike A schedule data, the output from the TSMS in the holding registers will be in the same format as seen by the EDAS feature, not in the OPM format.

7.05 The DOR measurements are collected and reported in groups of five registers. Each TSMS register and its associated number (00000 through 00255) is assignable by the user to a combination of an originating source and a destination for a specific type of call (eg, 1+, 0+, or local). Three software registers are associated with each TSMS register. These registers are (1) the peg count register, (2) the set-up usage (reported at a call record [CS] rate), and (3) the connect usage (reported at a CCS rate). The fourth entry that appears is total usage, set-up usage plus connect usage, and is reported at a CCS rate.

7.06 The DOR TSMS registers are reported in blocks of 32. In an entity where for example, only 10 registers are assigned, the first 10 (00000 through 00009) would contain data for the events that took place on the group during the reporting period. The unassigned registers (00010 through 00031) in the block will contain the unimplemented value of 65530. Figure 2 contains a sample D schedule from the DMS-10 switching system EDAS/TSMS output.

#### 8. DATA SUMMARIZATION

## A. Nonmechanized

8.01 It is the responsibility of the NSA to provide valid data in a mutually acceptable format which is usable by the receiving departments.

## 8. DATA SUMMARIZATION

## A. Nonmechanized

8.01 It is the responsibility of the NSA to provide valid data in a mutually acceptable format which is usable by the receiving departments.

forms to be used for manual posting and distributing of data when the DMS-10 switching system is in the nonmechanized mode. One data month can be posted on each form. The forms include some calculations designed for surveillance purposes and are self-explanatory in that each calculation is described in the form. All components should be recorded for the office busy hour. The forms for DIGITONE signaling receivers (Sheet 7) and MF receivers (Sheet 8) have provision for multiplying the average monthly usage times their individual component ratio as covered in paragraph 6.08. After 12 months of data have been accumulated on the forms, a blank form can be utilized to summarize the busy season for each item.

**8.03** Table D contains an index and the use of each form.

# B. Mechanized

8.04 As stated, the introduction of the EDAS feature in the DMS-10 switching system provides the ability to send formatted data to a collection device (eg, EADAS). This formatted data may then be split-off into sections. One split-off section will generally consist of trunking data and be sent to a sum-

marization system (eg, Trunk Servicing System [TSS]). If EADAS is the data collection system utilized, from an administrative point of view, there will be a combination of "automatic" features provided and "non-automatic" features.

- 8.05 Nontrunking data (eg, administrative data) is reformatted by EADAS and an E schedule is compiled. This data is the sole source of data for downstream processing by a data summarization, such as COER. This data contains the daily peak traffic values computed from measured hourly quantities, along with a "time stamp" to indicate the end of the hour for the data it represents.
- 8.06 The data summarization from COER will provide monthly and MLSS reports based on the data. Only data on the DMS-10 switching system processor is unique, in that the peak half-hour is utilized instead of the hourly summary. The reports generated are broken into two logical categories. Those reports used basically for administrative purposes, which will provide general information on the office; and those which will be utilized for administrative and engineering purposes to provide information on the engineerable components. The 12 items contained in the DMS-10 switching system COER reports are:
  - (a) Administrative items:
    - Office Information—Totals of network groups, lines (local and remote), modules, and main stations
    - Office Totals—O&I calls (DP + DGT and Total: (MF and total incoming)
    - Call Type Data—Total calls (peg counts and usage)
    - Attempts—Originating (originating, false starts, permanent signal, etc)
    - Attempts—Incoming (incoming, intercepted, blocked, etc).
  - (b) Administrative and engineering items:
    - Conference Circuits
    - DIGITONE Signaling Receivers
    - MF Receivers

- Analog Shelves (network usage on analog [lines and trunks] shelves)
- Digital Shelves (digital lines and trunks usage or digital shelves)
- Processor—Occupancy (by call types)
- Processor—Delay (by call types).
- 8.07 Figure 14 contains a set of COER outputs. Except for the office information report, all reports are available as monthly, intermediate, or MLSS reports. Office information is available only as a monthly report.
- 8.08 In addition to the COER output, the sheets in Fig. 11 contain the calculations utilized by the system to derive the results, where required. Several calculations are shown utilizing an alphnumeric representation. For example, 6 PESH NU may be interpreted to mean:

6 = a measurement in OPM 006

PESH = the peripheral shelf

n = an individual circuit or circuit group

U = a usage count register

- 8.09 When this interpretation is applied, the output of the EDAS feature cannot be used. If an analysis of data is required, the QUE prompt must be used on the system data blocks and compare OPM output to the COER and/or EDAS output. See Part 9 for further information on data analysis.
- 8.10 If the data summarization utilized is COER, consult the COER lessons for complete information on management of the data within the system. The COER lessons are similar to other systems and are easily interpreted. In order to set up the COER output shown in sheet 13 of Fig. 14, an ODF (Office Description File) is required. Table E contains the information required to establish a COER ODF. Specific information for ODF establishment and validation are found in the COER lessons.
- 8.11 At the present time, neither the data collection system (eg, EADAS) nor the data summarization system (eg, COER) have the ability to summarize special study requests. Until a reporting

and summarization module is available, any special studies will need to be performed manually. A request from the data collection system (eg, EADAS) should be performed at regular intervals by checking the contents of the A schedule, in particular the CLM (for individual customer lines) and the CGM (for hunt group information) sections. As an alternative, OPM data blocks OPM 007 and OPM 010 may be queried from the DMS-10 switching system holding register area. The data from OPM 007 and/or CLM may be entered and summarized on Data Summarization Form, Sheet 14 of Fig. 13. The data from OPM 010 and/or CGM may be entered and summarized on Data Summarization Form, Sheet 16 of Fig. 13.

# C. DMS-10 Switching System NSPMP Requirements

8.12 Section 241-140-005 contains the information required for the DMS-10 switching system NSPMP. This NSPMP, like the other NSPMPs, are performed on data based on the TCBH. The NSPMP section is written based on the OPM data. A comparison of the sections of the A schedule with the OPM output may be referenced in Fig. 15 of this section. For example, MF receiver overflows are taken from the OPM 005 "SVCE" printout (MFR OVFL), or CMP 00009 on the A schedule. These required measurements are based on the BHD study hours, and must be provided on a manual query of the office data.

#### 9. DATA ANALYSIS

- 9.01 As stated earlier, the responsibility of the NSA includes the validation of data, or data analysis regardless of the method used to collect the data, mechanized or nonmechanized. Valid data may be defined as data which supplies an accurate record of the performance of a switching machine and the trunk groups that permit the machine to communicate with other switching entities. Therefore, validation and reliability assurance could be described as a process of determining that the collected data are reasonably relating the actual performance of the switching machine and the associated machine trunking.
- 9.02 The procedure for validation is to determine if the data measurements are within expected limits, ie, a comparison of machine data against theoretical and/or historical and therefore expected values. In addition, assurance of data reliability is done by comparing specific register groupings against other register groupings. These procedures may be

done manually by making checks on selected items or groups of items. This procedure is based on past measurements, other measurements taken at the same time, knowledge of the equipment design and operation, experience, and judgment. Measurements which are within historical or theoretical limits may be accepted as reasonable. Those data which fall outside these limits should be considered questionable, and require further investigation.

- 9.03 When data reliability checks fail (ie, defined tolerances are exceeded), data validation techniques are applied to the individual registers within the register groupings to isolate specific areas of possible data problems. The possibility always exists that invalid data could be created by component malfunctions. Complete data analysis (validity checks and reliability tests) is the sure form of data evaluation.
- 9.04 The data for the DMS-10 switching system, like other electronic systems, is subject to some data distortion. Distortion can be caused by traffic skew or peakedness, skew caused by phases of a call, and the rounding effect of data calculations. Traffic skew is defined as a peak of traffic load offered to a switching system during a measurement period. It is possible that offered traffic load could increase dramatically in a given quarter-hour period. The data printout for that hour would indicate a load higher than a comparable hour where there is no peak traffic skew.
- 9.05 Skew caused by phases of a call occurs when registers are scored at various phases of a call. The data printout may not reflect all counts related to all of the calls in progress at the time of printing. This effect can cause peg and/or usage counts that cannot be accounted for when validation and reliability checks are applied to the data.
- 9.06 One of the first data analysis steps an NSA can take both on a regular ongoing basis and anytime the data is suspect is to look at a light load period. For example, a 4:00 am printout traditionally carries very little traffic, and data problems in individual registers are often easily detected.
- 9.07 Basic ongoing data validity checks include:
  - (a) **Holding Times** (Usage ÷ peg count × 100): Component or call holding times should be monitored on a constant basis and compared to

past data and to expected holding time values. For example, the expected holding time value for MF receivers must be greater than 0.6 and less than 12. In addition, if past data on an office showed an average MF receiver holding time of 2.38 seconds and the data showed a sudden increase to 8 seconds, the data would be suspect.

- (b) **Percentage of Occupancy** (Usage ÷ maximum usage possible × 100): The maximum usage that any component can generate in an hour is 36 CCS. Therefore, total usage measured on a service circuit group or a trunk group should not exceed 36 times the number of circuits.
- (c) CCS/MS and CALLS/MS: The CCS or calls per main station (MS) should approximate past history. A gradual increase or change can be expected, but a dramatic change for comparable business days might indicate a problem.
- 9.08 A data reliability tool that has historically proven useful is the traffic graphic. A basic traffic graphic is referred to as a "lazy H" pattern of call progression through a switching machine and is displayed as follows.

Originating Outgoing

Terminating IAO TANDEM (through) Incoming

- **9.09** The pattern can be used by making various comparisons. For example:
  - (a) Originating traffic minus intraoffice should approximate outgoing minus tandem (through)
  - (b) Terminating traffic minus intraoffice should approximate incoming minus tandem (through).
- 9.10 A more detailed method of data reliability can be accomplished using data reliability formulas. A formula simply makes a logical comparison of registers (or groups of registers) to other registers (or groups of registers). Figure 15 provides a set of data reliability comparison work sheets and are designed so that actual DMS-10 switching system data can be entered and comparisons made. These comparisons only address "approximations" as more de-

finitive tolerances will be developed later from actual data gathered from a number of DMS-10 switching system machines. The symbols used on the data reliability work sheets are as follows.

• The Sum of:	Σ
• Approximately Equal To:	≈
• Greater Than:	>
• Less Than:	<

#### 10. REFERENCES

10.01 The following Bell System Practices will aid the network administrator in accomplishing the required administrative functions. See Section 780-100-027 for a complete list of recommended documents.

SECTION	TITLE
241-120-010	Manual Office Records
241-120-011	Line and Number Administration
241-120-020	Translations
241-120-030	Data Modification Operations
241-120-050	Service Analysis
241-120-060	Machine Capacity Management
780-200-014	Determination of Line and Number Requirements
780-200-031	Busy Hour Determination—End Office

10.02 In addition, the following Northern Telecom Practices may be of use to the network administrators.

SECTION	TITLE
297-3001-060	Performance Oriented Practices User's Guide
297-3001-100	General Description
297-3001-105	Features and Services Description
297-3001-150	Equipment Identification

SECTION	TITLE	SECTION	TITLE
297-3001-181	Line Circuit Interface		
297-3001-182	Trunk Circuit Interface	297-3001-307	Line Load Control
297-3001-200	System Growth Practices	297-3001-311	Data Modification Manual
297-3001-300	Input/Output System		
297-3001-304	Data Modification—General	297-3001-456	Operational Measurements

TABLE A
OPERATIONAL MEASUREMENTS

DATA TYPE	MNEMONIC	EXPLANATION
Peg Count (Note 1)	PEG	A count of the number of times a particular event occurs.
Blockage	BLK	A count of the number of times call completion is unsuccessful due to the unavailability of some office resource.
Usage (Note 2)	USE	The length of time associated with particular events.
Request	REQ	A count of the number of requests for a particular resource.
All Resources Busy	OVFL	A count of the number of times a request for a particular resource is denied due to all all-items-busy condition.
Percent Service	%	The requests for a particular service that are delayed beyond a specified time interval. The delayed requests are expressed as a percentage (in units of 0.1 percent) of the total requests.
Maintenance Usage (Note 2)	MTCE	The amount of time circuits that have a maintenance usage counter are placed in a maintenance status. This status may be due to faults, man-made busy, machine-made busy. Usage associated with a test call or a component from an Incoming Test Trunk correction is excluded. Usage begins on activation of the maintenance status and ends when the circuit is returned to service.

# Notes:

- 1. Many peg counts are for successful counts only and will not include overflow or blockage counts.
- 2. Usage data are collected by scanning resources or components every 10 or 100 seconds to determine their busy/idle status. The result is expressed in hundred call seconds (CCS) to 0.1 CCS precision for the 10-second scan interval and 1.0 CCS precision for the 100-second scan interval.

TABLE B
"DMS"-10 SWITCHING SYSTEM
MEASUREMENT BLOCKS

MNEMONIC	DESCRIPTION	REQ	PEG	BLK	OVFL	USE	MTCE
-	OPM001 TRAFFIC DISTRIBUTION						
ORTM	ORIGINATING — TERMINATING		X	X		X	
OROG	ORIGINATING — OUTGOING		X	X		X	
ORNC	ORIGINATING — NONCOMPLETING		Х				
RVRT	REVERTIVE		Х			X	
INTM	INCOMING — TERMINATING		X	X		X	
INOG	INCOMING — OUTGOING		Х	X		X	
INNC	INCOMING — NONCOMPLETING		Х				

	OPM002 ORIGINATING SERVICE	****	
PSIG	PERMANENT SIGNAL	X	
PDTO	PARTIAL DIAL TIMEOUT	X	
PABN	PARTIAL DIAL ABANDON	X	
FSTR	FALSE START	X	
DGTC	DIGITONE CALLS	X	
DPC	DIAL PULSE CALLS	X	
тотс	TOTAL CALLS	X	
DGTS	DIGITONE DIAL TONE SPEED %	X	
DPS	DIAL PULSE DIAL TONE SPEED %	X	
TOTS	TOTAL DIAL TONE SPEED %	X	

OPM003 INCOMING SERVICE					
PSIG	PERMANENT SIGNAL	X			
PDTO	PARTIAL DIAL TIMEOUT	X			

MNEMONIC	DESCRIPTION	REQ	PEG	BLK	OVFL	USE	MTCE
	OPM003 INCOMING SERVICE (Contd)		-				
PABN	PARTIAL DIAL ABANDON		X				
HITS	HITS		Х				
MFRC	MF RECEIVER CALLS		X				
тотс	TOTAL CALLS		X				
RDLY	RECEIVER ATTACHMENT DELAY %		X				

	OPM004 TRUNK GROUPS				
OGP#	OUTGOING TRUNK GROUP NO.	X	X	X	X
IGP#	INCOMING TRUNK GROUP NO.	X		X	X

	OPM005 SERVICE CIRCUITS					
DGTR	DIGITONE RECEIVER	X	X	X	X	X
MFR	MF RECEIVER	X	X	X	Х	X
SNET	SERVICE (TOTAL OF ALL FOLLOWING)	X	X		X	
DSND	DIGIT SENDER	X	X		X	
BUSY	BUSY TONE	X	Х		X	
RNGB	RING BACK TONE	X	X		X	
RORD	REORDER TONE	X	X		X	
DIAL	DIAL TONE	X	X		X	
HOWL	HOWLER TONE	X	X		X	
HIGH	HIGH TONE	X	X		X	
LOW	LOW TONE	X	X		X	
CWT	CALL WAITING TONE	X	X		X	
SPDT	SPECIAL DIAL TONE	X	X		X	

MNEMONIC	DESCRIPTION	REQ	PEG	BLK	OVFL	USE	MTCE		
	OPM005 SERVICE CIRCUITS (Contd)								
CFMT	CONFIRMATION TONE	X	x			X			

	OPM006 NETWORK				
NTLP — N	NETWORK LOOPS				
SNWK	SERVICE NETWORK	X	X	X	X
CONF	CONFERENCE	X	Х	X	X
PESH	PERIPHERAL CIRCUIT	X	Х	X	X
JCTR — J	UNCTOR GROUPS				
GRP		X	Х	X	X

	OPM007 STUDY REGISTERS		
DN	INDIVIDUAL LINE DIRECTORY NO.	X	X
TG	INDIVIDUAL TRUNK GROUP TYPE	X	X

	OPM008 MAINTENANCE		
CNTL —	CONTROL EQUIPMENT		
CPU	CENTRAL PROCESSING UNIT	X	X
MEM	MEMORY	X	X
INI	INITIALIZATION	X	
NTWK -	NETWORK EQUIPMENT		
NSPK	NETWORK SIGNALING PACKS	X	X
NTLP	NETWORK LOOPS	X	X
IGS	INTERGROUP SWITCH PACKS	X	X
LPTS	LOOP TIME SLOTS	X	X
JRTS	JUNCTOR TIME SLOT PAIRS	X	X .

MNEMONIC	DESCRIPTION	REQ	PEG	BLK	OVFL	USE	MTCE
	OPM008 MAINTENANCE (Contd)						
PEQP — P	ERIPHERAL EQUIPMENT						
SCM	SUBSCRIBER CARRIER MODULES		X			X	
PSHF	PERIPHERAL SHELF		X			X	
DCM	DIGITAL CARRIER MODULES		X			X	
TRK	TRUNKS		X			X	
LINE	LINES		X			X	
RCVR	RECEIVERS		X			X	
PEPR	PERIPHERAL PROCESSOR PACK		X			X	

	OPM009 CAMA			
ANI	ANI CALLS	X		
ANFL	ANI FAILURE — LOCAL OFFICE	X		
ANFC	ANI FAILURE — CAMA OFFICE	X	·	
ONI	ONI CALLS	X		
PDIS	CAMA POSITION DISCONNECTS	X		
MCKF	MATCH CHECK FAILURES	X		
CLGF	CALLING CODE FAILURES	X		

	OPMO10 HUNT			
HTGP — H	IUNT GROUP			
XXX	HUNT GROUP NUMBER	X	X	

MNEMONIC	DESCRIPTION	REQ	PEG	BLK	OVFL	USE	MTCE
	OPM011 CUSTOM CALLING FEATURES						
CWAT	CALL WAIT ATTEMPTS		X				
CWAA	CALL WAIT ATTEMPTS ANSWERED		X				i
CFWA	CALL FORWARD ACTIVATIONS		X				
CFWD	CALLS FORWARDED		X			X	
SCLL	SPEED CALL LONG LIST CHANGES		X				
SCSL	SPEED CALL SHORT LIST CHANGES		X				
SPCL	SPEED CALLS LONG LIST		X			X	
SPCS	SPEED CALLS SHORT LIST		X			X	
3WC	THREE WAY CALLING		X	X		X	

	OPM012 CPU REAL TIME				
BKGD	BACKGROUND			X	

	OPM013 (WITH GENERIC 208)			
CFTF	STUCK COIN FIRST TRIAL FAILURE	X		

TABLE C

CONTROL DATA ITEMS
PROMPTS AND RESPONSES

ITEMS	PROMPT	OPTION RESPONSE
1	REG	CHG
2	TYPE	OMC
3	BLK	*TRAF (Traffic Distribution)
İ		*OSVC (Originating Service)
		*ISVC (Incoming Service)
1		TRK (Trunk Groups) (Note 1)
1		*SVCE (Service Circuits)
Ì		NTWK (Network) (Note 1)
		SREG (Study Registers) (Note 1)
		*MTCE (Maintenance)
1		CAMA (Centralized Automatic Message Accounting) (Note 2)
	]	HUNT (Hunt Groups) (Note 1)
		*CCF (Custom Calling Features)
		*CPU (CPU Real Time)
4	*UPDT	QRTR (Quarter Hour)
1		HALF (Half Hour)
1		HRHR (Hourly on the hour)
ł		HRHF (Hourly on the half hour)
1		DALY (Daily)
		DOWK (Day of the week)
5	*UPDY	If UPDT = DOWK, the mnemonic for the day(s) of the week updating occurs. Valid entries are SUN, MON, TUES, WED, THUR, FRI, and SAT.
6	*UPHR	If UPHR = DALY or DOWK, a number from 0 through 23. This specifies the hour of the day at which updating occurs.
7	*UMOD	The mnemonic for the update mode. Valid entries are:
		ADD—The value in the accumulating register is added to the value in the holding register.
		REP—The value in the accumulating register replaces the value in the holding register.

# Notes:

- 1 These blocks are variable, based on the quantities contained (eg, incoming trunk groups, study registers, etc).
- 2 CAMA (in non-mechanized)/AXB in mechanized, required *only* if the office is a CAMA office, *not* CAMA serving.
- \* When the DMS-10 switching system is equipped with the EDAS feature and it is activated, the prompts/option responses marked with an asterisk have no meaning, and are disabled.

# CONTROL DATA ITEMS PROMPTS AND RESPONSES

ITEMS	PROMPT	OPTION RESPONSE
8	*PRNT	The mnemonic for the printout schedule. Valid entries are:
		QRTR (Quarter Hour)
1		HALF (Half Hour)
		HRHR (Hourly on the hour)
		HRHF (Hourly on the half hour)
		DALY (Daily)
		DOWK (Day of the week)
		ONUP (Print on updating)
		NOPR (No print)
9	*PRDY	If PRNT = DOWK, the mnemonic for the day(s) of the week on which printing occurs. Valid entries are SUN, MON, TUES, WED, THUR, FRI, and SAT.
10	*STRT	If PRNT = DALY or DOWK, a number from 0 through 23.
11	*STOP	If PRNT = DALY or DOWK, a number greater than or equal to the number specified for STRT.
12	*PRCL	The mnemonic for TTY classes. This specifies what class of TTY is used for outgoing OPM data. Valid entries are:
		MTC (Maintenance)
		DMO (Data Modification)
İ		TRAF (Traffic)
13	*ZRPR	Yes or No. If Yes, the holding register is set to zero on printing. If No, the holding register value is left intact on printing.

<sup>\*</sup> When the DMS-10 switching system is equipped with the EDAS feature and it is activated, the prompts/option responses marked with an asterisk have no meaning, and are disabled.

TABLE D

INDEX—DATA
SUMMARIZATION FORMS

SHEET NUMBER	BLOCK MNEMONIC	USE
1	TRAF	Surveillance, Engineering
2	TRAF	Surveillance, Engineering
3	osvc	Surveillance, Engineering
4	ISVC	Surveillance, Engineering
5	TRK	Surveillance, Trunk Servicing
6	TRK	Surveillance, Trunk Servicing
7	SVCE	Surveillance, Engineering
8	SVCE	Surveillance, Engineering
9	SVCE	Surveillance, Engineering
10	SVCE	Surveillance, Engineering
11	SVCE	Surveillance, Engineering
12	SVCE	Surveillance, Engineering
13	NTWK	Surveillance, Engineering
14	SREG	Special Studies
15	CAMA	Surveillance, Engineering
16	HUNT	Special Studies
17	CCF	Surveillance, Engineering
18	osvc	Traffic Separations Monthly Peg Count

# TABLE E COER ODF CONTENTS REQUIREMENTS

## HEADER

Office Name

Generic/Issue

CLLI-DCU Code

Company ID

Batch Start Date

Batch End Date

Service Month End Day

Weekend Data (included or excluded)

EADAS generic

TNDS release

# OFFICE PARAMETERS

Total Network Groups

Line Concentration Ratio

Total Local (Analog) Lines

Total Remote (Digital) Lines

Number of Service Network Loops

Total DCMs

Total REMs

**Total SCMs** 

Office Trunks

Digital Trunks

**Analog Trunks** 

PBX Trunks

Dial Pulse (DP) Trunks

#### **COER ODF CONTENTS REQUIREMENTS**

## OFFICE PARAMETERS (Contd)

Office Main Stations (MS)

Digital MS

Analog MS

PBX MS

Coin MS

DP MS

## "DIGITONE" SIGNALLING RECEIVERS

Number of DIGITONE Signalling MS

Number of DGT Receiver Circuits Installed

DIGITONE Signalling Receiver Engineered Capacity

# MF RECEIVERS

Number of MF Trunks

Number of MF Receiver Circuits Installed

MF Receiver Engineered Capacity

# CONFERENCE NETWORK

Number of Conference Circuit MS

Number of Conference Circuits Installed

Conference Circuit Engineered Capacity

# NETWORK GROUP PARAMETERS (PER NETWORK GROUP)

Network Groups (1-3):

Number of Peripheral Circuits (PCKT) in Group and is PCKT Digital or Analog

# TRUNK GROUP PARAMETERS (PER INCOMING TRUNK GROUP/OUTGOING TRUNK GROUP):

Number of Incoming Trunk Groups, and is each ITG Digital or Analog


Number of Outgoing Trunk Groups, and is each OTG Digital or Analog

	MSG A	SNAM	TXRRCGO	1T2 08:	30 06	/02/83<	eol>			
VAL	00005	00001	00002	00003	00004	00005<				
OFT	00033	00001	00002	00003	00004	00005	00006	00007	00008	00009 <eo1></eo1>
0	00010	00011	00012	00013	00014	00015	00016	00017	00018	00019(eo1)
	00020	00021	00022	00023	00024	00025	00026	00027	00028	00029(eo1)
	00030	00031	00032	00033<						
FEA	00017	00001	00002	00003	00004	00005	00006	00007	00008	00009(eo1)
	00010	00011	00012	00013	00014	00015	00016	00017<		
PRO	00003	00001	00002	00003						
CMP	00046	00001	00002	00003	00004	00005	00006	00007	00008	00009 <eo1></eo1>
0	00010	00011	00012	00013	00014	00015	00016	00017	00018	00019(eo1)
	00020	00021	00022	00023	00024	00025	00026	00027	00028	00029 <eo1></eo1>
	00030	00031	00032	00033	00034	00035	00036	00037	00038	00039(eo1)
	00040	00041	00042	00043	00044	00045	00046<			
SNW	00005	00001	00001	00002	00003	00004	00002	00001	00002	00003(eo1)
<b>D.</b> 1111	00004	00003	00001	00002	00003	00004	00002	00001	00002	00003(eo1)
	00004<						•			
CON	00005	00001	00002	00003	00004	00005	65530	65530	65530	65530 <eo1></eo1>
00	65530<									
PCK	00060	00001	00002	00003	00004	00005	00006	00007	00008	00009 <eo1></eo1>
. 0	00010	00011	00012	00013	00014	00015	00016	00017	00018	00019 <eo1></eo1>
	00020	00021	00022	00023	00024	00025	00026	00027	00028	00029(eo1)
	00030	00031	00032	00033	00034	00035	00036	00037	00038	00039(eo1)
	00040	00041	00042	00043	00044	00045	00046	00047	00048	00049 <eo1></eo1>
	00050	00051	00052	00053	00054	00055	00056	00057	00058	00059(eo1)
	00060<									
JTR	00005	00001	00002	00003	00004	00005<	eo1>			
CGM	00003	00001	00002	00003	00006	00002	00003	00008	00002	00003(eo1)
· · · · · ·	65530	65530	65530	65530	65530	65530	65530	65530	65530	65530(eo1)
	65530	65530	65530	65530	65530	65530	65530	65530	65530	65530(eo1)
	65530	65530	65530	65530	65530	65530	65530	65530	65530	65530(eo1)
	65530	65530	65530	65530	65530	65530	65530	65530	65530	65530(eo1)
	65530	65530	65530	65530	65530	65530	65530	65530	65530	65530(eo1)
	65530<			*						
CLM	00003	00001	00002	00003	00005	00002	00003	00006	00002	00003 <eo1></eo1>
	65530	65530	65530	65530	65530	65530	65530	65530	65530	65530 <eo1></eo1>
	65530	65530	65530	65530	65530	65530	65530	65530	65530	65530(eo1)
	65530	65530	65530	65530	65530	65530	65530	65530	65530	65530 <eo1></eo1>
	65530	65530	65530	65530	65530	65530	65530	65530	65530	65530(eo1)
	65530	65530	65530	65530	65530	65530	65530	65530	65530	65530(eo1)
	65530<									
TKO	00005	00043	00002	00003	00004	00005	00044	00002	00003	00003 <eo1></eo1>
	00004	00005	(eo1)							
TKI	00004	00043	00002	00003	00004<	eo1>				
AXA	00029	00001	00002	00003	00004	00005	00006	00007	00008	00009(eo1)
	00010	00011	00012	00013	00014	00015	00016	00017	00018	00019(eo1)
	00020	00021	00022	00023	00024	00025	00026	00027	00028	00029(eo1)
AXB	00007	00001	00002	00003	00004	00005	00006	00007<		-
END<										
	. –									

Fig. 1—Sample A Schedule, DMS-10 Switching System EDAS Feature Output (3.03, 5.14, 6.12)

```
MSG D SNANTXRRCG01T2 09:00 06/02/83(eo1)
VAL
      00005 00001 00002 00003 00004 00005(eo1)
DOR
      00005
            00001 00002
                          00003
                                 00004
                                        00005
                                               00001 00002 00003 00004(eo1)
      00005
            00001
                   00002
                          00003
                                 00004
                                        00005
                                               00001 00002
                                                             00003
                                                                    00004<eo1>
      00005
            00001 00002
                          00003
                                 00004
                                        00005
                                               00001
                                                     00002
                                                             00003
                                                                    00004<eo1>
      00005
            65530 65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                             65530
                                                                    65530(eo1)
      65530
             65530 65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                             65530
                                                                    65530<eo1>
             65530 65530
                                 65530
                                        65530
                                               65530
                                                      65530
      65530
                          65530
                                                             65530
                                                                    65530 (eo1)
      65530
             65530 65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                             65530
                                                                    65530(eo1)
             65530
                   65530
                          65530
                                 65530
                                        65530
                                                      65530
      65530
                                               65530
                                                             65530
                                                                    65530(eo1)
      65530
             65530 65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                             65530
                                                                    65530 < eo1 >
      65530
             65530 65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                             65530
                                                                    65530<eo1>
             65530 65530
      65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                             65530
                                                                    65530(eo1)
      65530
             65530 65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                             65530
                                                                    65530 (eo1)
      65530
            65530 65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                             65530
                                                                    65530<eo1>
                                                             65530
      65530
            65530
                   65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                                    65530(eo1)
      65530
            65530 65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                             65530
                                                                    65530(eo1)
      65530 65530 65530
                          65530
                                 65530
                                        65530
                                               65530
                                                      65530
                                                             65530
                                                                   65530(eo1)
      65530 (eo1)
END(eo1)
```


Fig. 2—Sample D Schedule, DMS-10 Switching System EDAS/TSMS Feature Output (3.03, 7.06)



# LEGEND:

- 1) MEASUREMENT BLOCK CODE
- (2) BLOCK MNEMONIC
- (3) CENTRAL OFFICE IDENTIFICATION MNEMONIC
- (4) UPDATE DAY
- (5) UPDATE DATE
- (6) UPDATE TIME
- (7) UPDATE PERIOD
- (8) COLUMN HEADERS
- (9) LINE LABELS

Fig. 3—Operational Measurements Block Printout Format (4.14)



# NOTES:

- 1. Data is transferred per NTP 297-3001-456, OPM format.
- Data is transferred directly to I/O for EDAS formatting (no corresponding holding registers).
- On demand, the data request accesses the holding registers and is output to the terminal in the OPM format.
- Formatted data is output to the terminal in the A-schedule and D-schedule format on a unidirectional outgoing channel

Fig. 4—Operational Measurement Data Flow—Mechanized and/or Nonmechanized (4.14, 5.03)

SYSTEM PROMPT	USER ENTRY
!	LOGI < CR>
PASS?	XXXX (Password) < CR>
LOGI TRAF	
#	OVLY OMC < CR >
OMCOOO OMC	
REQ	QUE OMC < CR>
BLK TRAF	
UPDT QRTR	
UMOD ADD	
PRNT HRHR	
PRCL TRAF	
ZRPR YES	
REQ	***
#	LOGO < CR>
!	

Fig. 5—Example of TTY Session to Query Control Data Items for Measurement Blocks (4.19)

FORM: OMC DMS-10 DATE **DVLY: OMC** OPERATIONAL MEASUREMENT CONTROL ORDER NUMBER OFFICE SH \_ OF \_ RECENT CHANGE ORDER REQ ō TYP BLK UPDT UPDY UPHR UMOD PRNT PRDY STRT STOP **PRCL** ZRPR 0 0 7 9 2 2 2 4 2 2 7 9 3 3 2 4 5 5 7 9 3 3 7 9 4 4 7 9 5 5 2 4 1 1 7 9 4 4 2 4

Fig. 6—Recent Change Order—Operational Measurement Control (4.19)

SYSTEM PROMPT	USER ENTRY							
!	LOGI <cr></cr>							
PASS?	XXXX (Password) < CR>							
LOGI TRAF								
#	OVLY OMC < CR>							
омсооо омс								
REQ	CHG < CR>							
TYP	OMC <cr></cr>							
BLK	TRAF < CR>							
UPDT	QRTR < CR>							
UMOD	ADD <cr></cr>							
PRNT	HRIIR < CR>							
PRCL	TRAF < CR>							
ZRPR	YES < CR>							
REQ	***							
#	LOGO < CR>							
!								
Note: In the above session, all items were changed.								
If an item is not changing, a response of CR will								

Fig. 7—Example of TTY Session to Change Control Data Items of Measurement Blocks (4.19)

leave it the way it was.

DMS-10 STUDY REGISTER

DATE ORDER NUMBER

OFFICE														RECENT CHANGE ORDER											SH _ OF _																			
					BSPU																																							
REQ		TY	/P		Τ,	ΥP		В	ΑY		S H F			P A C K		N I T		SP	N	0																					<u> </u>			
0 0 1 3	0 5 S			0 8	1 0	1		1 3	1 4		1 6		1 8	1 9		2	2 3	2	2 6	2 7						·																		_
	S	R	E	G		_	<u></u>	L	1_	<u> </u>	↓_	<u> </u>	<u> </u>	<u> </u>	_	<u> </u>	<u> </u>	<u> </u>	1_	辶	┺	<u> </u>								_	_	_	1	$\perp$	┸	4	┸	1_	4_	1_	<u> </u>		$\sqcup$	_
1-1-	▙	Щ			L_		<u> </u>	ــــ	ļ	┞	-	<u> </u>	<u> </u>	<u> </u>	┡	1	ļ	L	↓_	$\perp$	╀		Ш	Щ				_	-	-		4	-	+	4	- -	4-	+	-	↓_		-	$\dashv$	_
1-1-1-	-	$\vdash$		-			-	<del> </del>	<del> </del>	╀	┼	├	⊢	⊢	┢	⊢	┢	├	╀	╀	┼	-	-							$\dashv$	$\dashv$	+		- -	+	╁	+	╀	+	╀	$\vdash$			-1
J <del>-1-1-</del>	┼	Н	-	-		-	$\vdash$	$\vdash$	┢	┼	$\vdash$	├─	-	├	├	╂	├	-	╁╌	╁	╀	-	H	$\vdash$			-	$\dashv$	$\dashv$	-+	$\dashv$	+	+	╁	╁	+	╁	╁	+	╁─		Н	$\dashv$	-
1 + 1	-	-				╁	├	-	┼─	-	╁╴	-	╁	H	<del>                                     </del>	<del>  -                                    </del>	-	H	╁	┢	+		H						-	┪	+	+	十	+	╁	╁	†-	╁╴	╁╌	+-		Н	-	-
							$\vdash$	$\vdash$		<u> </u>	1		┢	┪	1		⇈	一	1	†	†	1							_	寸	$\dashv$	$\top$	$\top$	十	$\top$	$\top$	†	T	†	1				-
								$\vdash$	厂	$\vdash$	$\vdash$				1			Π	1														$\top$											
																															$\Box$		$\perp$	$\perp$	$\perp$		$\Gamma$	L						_
				[						L							$ldsymbol{ld}}}}}}$	_	L	L	<u> </u>		Щ	$\Box$	_	_	_	$\dashv$	_	_	$\dashv$	$\bot$	$\perp$	$\perp$	$\perp$	L	1_	┸		L	Ш		4	_
1	-	_	_						L	<u> </u>	<u> </u>	L_	_	<u> </u>	L	L	L	<u> </u>	<u> </u>		<u> </u>				_	_	$\dashv$	_	_	4	4	4	4-	4-	╀	╀	↓_	↓_	₩		Щ	_	-	_
1-1-1-	Н							ļ		_	<del>  -</del>	_		<b> </b>	<u> </u>	<b> </b> -	├	⊢		┞	<u> </u>	_			-			$\dashv$	-	4	+	+	+	+		╀	+-	╀	╀	├	-		$\dashv$	-
<u> </u>	$\vdash$	-		-	-			Н		⊢	$\vdash$	<u> </u>		<u> </u>	_	⊢	<b> </b>		-	-	╂┈			$\dashv$			-	1		-	+		+	╁	╁	╂	╁	╁	╁─	├	Н	$\dashv$	$\dashv$	-
I <del>-I-I-</del>	-		$\dashv$	$\dashv$		$\dashv$	$\vdash$	Н	H	-	$\vdash$	-		├	<b> </b> -			-	├	┢	├-	-			$\dashv$	$\dashv$	$\dashv$	-	$\dashv$	$\dashv$	+	╁	+-	+-	╁╌	╁╾	╁	╁	╁	╁	Н	$\dashv$	$\dashv$	-
1 <del>-1-1</del>			+						-	-	<del> </del>	-		-	<del> </del>		<del> </del>	┢	$\vdash$	$\vdash$	+	Н	$\vdash \vdash$	$\dashv$		-	$\dashv$	$\dashv$	$\dashv$	$\dashv$	十	+	十	+	+-	+-	+	$t^-$	$\vdash$	-	$\vdash$		$\dashv$	-
1-1-1-1	$\vdash$	-	-+	+	-		$\dashv$	-i	-	-	$\vdash$		$\vdash$	<del> </del>	-	<del>                                     </del>	<del>                                     </del>	_	$\vdash$	-	1	Н	$\vdash$				_	_	$\dashv$	$\dashv$		+	+	$\top$	1	1	$\top$	†	1		$  \neg  $		$\dashv$	-
1-1-1-1	$\vdash$	_		$\dashv$	_					$\vdash$		-	$\vdash$			T			1	T	<u> </u>	$\vdash$		7	一	_	寸		7	$\dashv$	十	1	十	1	1	T	1		1		П			
	$\Box$	1	1	寸							П						<u> </u>		Γ			П		7	_				丁		$\perp$				Γ									_
																											$\Box$		$\Box$	$\Box$	$\Box$	I	I										$\Box$	_
				T																							$\Box$																	

Fig. 8—Recent Change Order—Study Register (4.19)

SYSTEM PROMPT	USER ENTRY
	LOGI < CR>
PASS?	XXXX (Password) < CR>
LOGI TRAF	
#	OVLY OMC < CR >
омсоо омс	
REQ	ADD < CR>
TYP	SREG <cr></cr>
BSPU	PE 08 2 03 01 <cr></cr>
REQ	****
#	LOGO < CR>
!	

Fig. 9—Example of TTY Session to Add a Study Register (4.19)

DATE\_\_\_\_\_ORDER\_NUMBER\_ DMS-10 FORM: OMPH OPERATIONAL MEASUREMENTS HUNT GROUP OVLY: OMC OFFICE\_ SH \_ OF \_ RECENT CHANGE ORDER REQ TYP HTGP 0 0 4 6 0 1 9 1

Fig. 10—Recent Change Order—Operational Measurements Hunt Group (4.19)

SYSTEM PROMPT	USER ENTRY
1	LOGI < CR>
PASS?	XXXX (Password) < CR>
LOGI TRAF	
#	OVLY OMC < CR>
омсооо омс	
REQ	ACT < CR >
ТҮР	HUNT < CR>
HTGP	1 <cr></cr>
REQ	***
#	LOGO < CR>
!	

Fig. 11—Example of a TTY Session to Activate a Hunt Group (4.19, 8.08)




Fig. 12—DMS-10 Switching System Data Output Formats (Sheet 1 of 4) (5.13, 5.15, 6.12, 6.14, 6.16, 8.12)





Fig. 12—DMS-10 Switching System Data Output Formats (Sheet 2 of 4) (5.13, 5.15, 6.12, 6.14, 6.16, 8.12)



<sup>(1)</sup> Indicates the number of entries per section/group.
\* 1st entry = 00003, indicates 3 data items in each record.
On OPM printout, 3 hunt groups are defined. EDAS feature outputs records in blocks of 20. Those hunt groups not defined contain and "unimplemented" value of 65530. If no hunt groups are defined, the CGM is not sent from the EDAS formatting area of the I/O.

Fig. 12—DMS-10 Switching System Data Output Formats (Sheet 3 of 4) (5.12, 5.15, 6.12, 6.14, 6.16, 8.12)




Fig. 12—DMS-10 Switching System Data Output Formats (Sheet 4 of 4) (5.12, 5.15, 6.12, 6.14, 6.16, 8.12)

#### DMS-10 DAILY DATA RECORD TRAF

BUSY/HOUR

NTITY				TRAFF	IC DISTRIE	BUTION		MONT	H & YEAR	
OPM -		ORTM		HT		OROG		нт	ORNC ORIG NON COMP	INNC INC NON COMP
001	ORI	GINATING-TERM	INATING	USE ÷ PEG X	ORIG	INATING-OUTG	GOING	USE ÷ PEG X		
DATE	PEG	BLK	USE	100	PEG	BLK	USE	100	PEG	PEG
		1							<b></b>	
		-							ļ	
		<del> </del>	<u> </u>							
										<del></del>
		:								
		ļ								
		ļ								
		<del> </del>				•				
				† †						
TOTAL										
AVERAGE		J BLK ÷ PEG + B								

Fig. 13—Data Summarization Form (Sheet 1 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

ISS 2, BR 241-120-040

BUSY HOUR \_\_\_

# DMS-10 DAILY DATA RECORD TRAF

ENTITY				T	RAFFIC DI	STRIBUTIO	N		MONTH 1	S YEAR	
OPM	RVRT		HT	INTM			HT	INOG			HT
001	REVERTIVE		USE ÷ PEG X		ING-TERMIN	ATING	USE ÷ PEG X		NG-OUTGOING	<b>†</b>	USE ÷ PEG X
DATE	PEG	USE	100	PEG	BLK	USE	100	PEG	BLK	USE	100
		ļ	ļ								
	<u></u>	<u> </u>	┦								
		<u> </u>	<del> </del>		·						
			<del>                                     </del>		· · · · · · · · · · · · · · · · · · ·		<del>                                     </del>				
					<del></del>						
			1								
			ļ <b>.</b>				<u> </u>				
			<del>                                     </del>		<del></del>		<b></b>			·	
						<u> </u>	<del> </del>				
	<del> </del>		<del>                                     </del>		<u></u>	<del></del>	<del>  </del>				
	<del>                                     </del>		<del>                                     </del>				<del>                                     </del>				
1 <u> </u>	<del></del>		1								
			1		· · · · · · · · · · · · · · · · · · ·						
							<u> </u>				
TOTAL							<del></del>				
AVERAGE			<del>                                     </del>			<del></del>					
NOTES:	L	-	<u> </u>	YRI K	(BLK + PEG	+ BIK X 100	) %BLK				
HOILU.					,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	55 X 100		_			

Fig. 13—Data Summarization Form (Sheet 2 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

### DMS-10 DAILY DATA RECORD

OSVC BUSY HOUR \_ ORIGINATING SERVICE MONTH & YEAR

ITITY				ORIG	INATING SE	MONTH & YEAR				
OPM	PSIG	PDTO PARTIAL	PABN PARTIAL	FSTR	DGTC	DPC DIAL	тотс	DGTS	DPS DIAL	TOTS
002	PERMANENT Signal	DIAL TIMEOUT	DIAL ABANDON	FALSE Start	DIGITONE Calls	PULSE CALLS	TOTAL Calls	DIGITONE DTS%	PULSE DTS%	TOTAL DTS%
DATE	PEG	PEG	PEG	PEG	PEG	PEG	PEG	PEG	PEG	PEG
							<del>                                     </del>			<u> </u>
						-				
	-		<del>  </del>							
								^		
OTAL										
ERAGE	<del>                                     </del>		<del>                                     </del>						· · · · · · · · · · · · · · · · · · ·	

BUSY HOUR \_

## DMS-10 DAILY DATA RECORD ISVC

ENTITY			INCOM	ING SERVICE		MONTH & YEA	R
0PM 003	PSIG PERMANENT SIGNAL	PDTO PARTIAL DIAL TIMEOUT	PABN PARTIAL DIAL ABANDON	HITS HITS	MFRC MF RECEIVER CALLS	TOTC TOTAL CALLS	RDLY RECEIVER ATTACHMENT DELAY %
DATE	PEG	PEG	PEG	PEG	PEG	PEG	PEG
DATE	7.20	120	l				
						•	
		<u> </u>					
				·			
TOTAL							
AVERAGE							
NOTES:							

Fig. 13—Data Summarization Form (Sheet 4 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

TRUNK GROUPS MONTH & YEAR \_ ENTITY\_ нт HT 0PM OGP# \_\_\_\_ OGP# \_\_\_\_\_ OGP# \_\_\_\_ USE ÷ USE ÷ 004 USE ÷ OGP NAME OGP NAME OGP NAME \_ PEG X PEG X PEG X PEG USE 100 PEG OVFL USE 100 DATE OVFL PEG OVFL USE 100 TOTAL AVERAGE NOTES:

BUSY HOUR \_\_\_\_\_

## DMS-10 DAILY DATA RECORD TRK

ENTITY					TRUNK GROUI	<i>PS</i>		MONTH & YEAR _	
OPM	IGP#		нт	IGP#		нт	IGP#		HT
004	IGP NAME		USE ÷ PEG X	IGP NAME		USE ÷ PEG X	IGP NAME		USE ÷ PEG X
DATE	PEG	USE	100	PEG	USE	100	PEG	USE	100
		<u> </u>							
	<u> </u>	ļ							<u> </u>
		<del></del>					<u> </u>		
		——			<del></del>				
	_ <b>_</b>						<b> </b>		
		<del> </del>				<del></del>			
	<u> </u>	<del></del>			<b></b>				
<u> </u>		<b></b>	4	<u> </u>	<del></del>				<del></del>
	<u> </u>			<u> </u>	<b></b>				<del></del>
	<u> </u>	<b>↓</b>		<b></b>		1			<del></del>
	<u> </u>								<del>- </del>
	'	<del></del>	1	<u> </u>	<del></del>				
<b></b>	<del></del> '	<del></del>	+	<u> </u>	<del>-</del>				<b>_</b>
<b></b> _	<u> </u>	<del></del>		<u> </u>	<del></del>		<b> </b>		<u> </u>
<b></b>	<u> </u>	<u> </u>	<del></del>	<b></b>	<del></del>	-	<u> </u>		<del>                                     </del>
<u> </u>	<b></b> '	<u> </u>							
	<del></del> '	<u> </u>	1			1	<u> </u>	<del></del>	
L	<b></b> ′	<del> </del>	4				<u> </u>		
<u> </u>	<b></b> '	<b></b>		<u> </u>	<del></del>	1	<u> </u>		
	<del>                                     </del>	<del> </del>	4	<u> </u>	<del></del>				
L	<b></b> '	ļ		<u></u>			<u> </u>		
TOTAL	<u> </u>	ļ		<u> </u>	<del></del>				
AVERAGE		<u> </u>			_ <u></u>		<u></u>		
NOTES:									

Fig. 13—Data Summarization Form (Sheet 6 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

SERVICE CIRCUITS MONTH & YEAR \_\_\_\_\_ ENTITY\_ DGTR HT OPM DIGITONE RECEIVER 005 USE ÷ A. NUMBER OF CIRCUITS PEG X DATE REQ PEG USE OVFL 100 B. CCS CAPACITY C. WORKING LINES D. COMPONENT BUSY HOUR RATIO (SEE PARAGRAPH 6.08) E. USAGE AVERAGE (X COMPONENT RATIO) F. CCS/LINE (E ÷ C) G. % CAPACITY (E ÷ B X 100) H. % OVERFLOW (TOTAL OVFL + PEG + OVFL X 100) TOTAL AVERAGE NOTES:

#### DMS-10 DAILY DATA RECORD SVCE

				9	SVCE	BUSY HOUR
ENTITY				SERVIC	CIRCUITS	MONTH & YEAR
OPM	MFR				нт	
005	MF RECEIVER				USE ÷ PEG X	A. NUMBER OF CIRCUITS
DATE	REQ	PEG	USE	OVFL	100	
			•			B. CCS CAPACITY
			•			
			•			
	<b>.</b>		•			C. WORKING LINES
			•			
	<u> </u>					
	<del>                                     </del>		•			D. COMPONENT BUSY HOUR
	<del> </del>		•			RATIO (SEE PARAGRAPH 6.08)
			•			
			•			E. USAGE AVERAGE
			•			(X COMPONENT RATIO)
			•			
			•			F. CCS/LINE
			•			(E ÷ C)
					<b></b>	
			-			G. % CAPACITY
			-			(E ÷ B X 100)
			•	<u></u>		
			•			H. % OVERFLOW
			•			(IDIAL OVEL + PEG + OVEL X 100)
			•			
TOTAL			•			
AVERAGE			•			
NOTES:					j	

Fig. 13—Data Summarization Form (Sheet 8 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

# DMS-10 DAILY DATA RECORD SVCE

BUS	Y HOUR
MON	TH C VEAD

ENTITY		<del>-</del>			SERV	ICE CIRC	MONTH & YEAR					
OPM 005	SERVICE NETWORK			HT USE ÷ PEG X	DSND DIGIT SENDER			HT USE ÷ PEG X	USE ÷ BUSY			
DATE	REG	PEG	USE	100	REG	PEG	USE	100	REG	PEG	USE	PEG X 100
			•				•				•	
			•				•				•	
			•	L			•				•	
· <u> </u>			•		<b>!</b>		•				•	
			•				<del></del> -		<b> </b>		•	
				 	<del> </del>		•		<del> </del>			
			•				•	ļ			•	
	<del> </del>		<del></del>				•	<u> </u>			•	
			•		<b>†</b>		•		<del>                                     </del>		•	
			•				•				•	
			•				•				•	
			•				•				•	
			•				•				•	
			•				<u> </u>		<u> </u>		•	
	<u> </u>		•				•		ļ		•	
		<u> </u>	•		<b></b>		•	ļ	<u> </u>		•	
					<u> </u>		•		<u> </u>			
<del></del>			•				•					
	<del> </del>		•				•		<b>-</b>			
	<del>                                     </del>		•		<del>                                     </del>		•					
			•	-			•	-			•	
TOTAL			•				•	.,			•	
AVERAGE			•				•				•	
NOTES:												

Fig. 13—Data Summarization Form (Sheet 9 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

BUSY HOUR \_\_\_\_\_

# DMS-10 DAILY DATA RECORD

SVCE	
SERVICE CIRCUITS	

ENTITY		<del></del>			SERV	ICE CIRC	UITS			MONTH &	YEAR	
0PM 005	RNGB RINGBACK	TONE		HT USE ÷ PEG X	RORD REORDER T	ONE		HT USE ÷ PEG X	USE ÷ DTAL TONS			USE ÷ PEG X
DATE	REG	PEG	USE	100	REG	PEG	USE	100	REG	PEG	USE	100
			•				•				•	
			•				•				•	
			•				•				•	
			•				•	<u></u>	<u> </u>		•	
			•				•				•	
	<u> </u>		•				•				•	
	<del></del>		•				-				•	
	<del> </del>						<u> </u>					
	<del>-</del>		-				-					
	<del> </del>		•		<u> </u>		-				•	
	<del> </del>		-				-			·	•	
	<del>                                     </del>										-	
	<del> </del>		•				•		<del> </del>		•	
<del></del>	<del>                                       </del>				l ——		•					
	<del> </del>		•								•	
			•				•				•	<del></del>
	<del> </del>		•				•				•	
			•				•				•	
	1		•				•			-	•	
			•				•				•	
			•				•				•	
			•				•				•	
TOTAL			•				•				•	
AVERAGE			•				•				•	
NOTES:								·				

Fig. 13—Data Summarization Form (Sheet 10 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

### DMS-10 DAILY DATA RECORD

SVCE BUSY HOUR \_\_\_\_\_\_
SERVICE CIRCUITS MONTH & YEAR

ENTITY					SERV	ICE CIRC	WITS .			MONTH &	YEAR	
0PM 005	HOWL Howler			HT USE ÷ PEG X	HIGH HIGH TONE			HT USE ÷ PEG X	LOW TONE			HT USE ÷ PEG X
DATE	REG	PEG	USE	100	REG	PEG	USE	100	REG	PEG	USE	100
			•				•				•	
			٠				•				•	
			•				•				•	
			•			<u> </u>	•				•	
			•				٠				•	
		<u> </u>	•				•				•	
		ļ <u>.</u>	•				•				•	
	<u> </u>		•				•				•	
		ļ	•				•			·	•	
			•								•	
	<b>.</b>	1	•								•	
	-	<del> </del>					•		ļ		•	
	1						•				•	
			<del>                                     </del>				•				•	
			<u> </u>				•				•	
	-	<b></b>	<u> </u>				•				•	
	<del> </del>		<u> </u>	-			•				•	
	<del> </del>		<del>                                     </del>				•					
	· <b>.</b>						•				•	
			-				•				•	
	<b>-</b>	ļ					•				•	
	<b></b>	ļ	<u> </u>				•				•	
TOTAL			•				•		ļ		•	
TOTAL	ļ		•				•				•	
VERAGE		<u> </u>	1						ļl		<u> </u>	
NOTES:												

Fig. 13—Data Summarization Form (Sheet 11 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

ENTITY\_\_\_\_

### DMS-10 DAILY DATA RECORD SVCE

SVCE	BUSY HOUR
SERVICE CIRCUITS	MONTH C VEAD

					SERVICE CIRCUITS					MONTH & TEAR			
0PM 005	CWT CALL WAITING TONE			HT USE ÷	SPDT SPECIAL I	DIAL TONE		USE ÷ PEG X CONFIGURATION TONE				HT USE ÷	
DATE	REG	PEG	USE	PEG X 100	REG	PEG	Lucr	100			LIOE	PEG X 100	
DATE	REG	PEG	USE	100	KEG	PEG	USE	100	REG	PEG	USE	100	
	ļ	<u> </u>	<del>                                     </del>		ļ		-				•		
	<del> </del>		-		<b></b>		-				•		
	<del> </del>	<u> </u>	-			<u></u>	•				•		
			-								•		
*****	<del> </del>	<u> </u>	-				•				•		
			-			<u> </u>	•	- "			•	L	
	<u> </u>	L	•			<u> </u>	•				•		
		<u> </u>	-				•				•		
		<b>_</b>	<u> </u>	<u> </u>	<u> </u>						•		
	<u> </u>		•			<del></del>					•		
	<u> </u>		-								•		
			•			<del></del>	-		ļ		•		
	ļ		•				-				•		
	ļ		-				-				•		
	<u> </u>		•								•		
	<u> </u>	-	•				•				•		
	ļ		•								•		
	<del> </del>	Ĺi	•			.,	•				•		
	<b>ļ</b>	ļ									•		
	<b>↓</b>	ļ	•				•				•		
· ·	ļ										•		
<u></u>			•				•			***************************************	•		
T0741							•				•		
TOTAL			•				-	·			•		
VERAGE	<u> </u>		•						<u> </u>		•		
OTES:													

Fig. 13—Data Summarization Form (Sheet 12 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

ENTITY						MORK (NT	'A RECORD 'WK)		BUSY HOUR Month & Year				
0PM 006	SNWK SERVICE TOTAL	NETWORK	<u>.                                  </u>	CONF CONFERENC TOTAL	<b>E</b>		PESH PERIPHERA TOTAL	L CIRCUIT		JCTR JUNCTOR GROUPS TOTAL			
DATE	PEG	BLK	USE	PEG	BFK	USE	PEG	BLK	USE	PEG	BLK	USE	
	<u> </u>							<u> </u>					
		ļ	Ļ	<u> </u>			ļ	ļ		<u> </u>	<u> </u>		
	<u> </u>		ļ				<b>_</b>				ļ <u>.</u>		
	<u> </u>		<del> </del>	<u> </u>			<u> </u>	<del> </del> _		<u> </u>	<u> </u>		
	<u> </u>	<del> </del>	<del> </del>			<u> </u>		<u> </u>		<del> </del>	<del> </del>	<u> </u>	
	<b>-</b>		<u> </u>	<del></del>	<u> </u>	<del> </del>	<del> </del>	<del></del>		<del> </del>		<b> </b>	
	<del> </del>	<del> </del>	<del> </del>	<del>-</del>	<del> </del>	<del> </del>	<del> </del>			<del> </del>	ļ		
	<del></del>	-}	┼───	}		<del> </del>	<del> </del>	<del> </del>		<u> </u>	<del> </del>		
	<del>                                     </del>	<del> </del>	<del> </del>	+			<del></del>	<del>                                     </del>	<u> </u>		<del> </del>	<del></del>	
	<del>                                     </del>	+	<del> </del>	<del> </del>	<u> </u>	<del>                                     </del>	<b> </b>			<b> </b>	<del>                                      </del>	<u> </u>	
	·	+	<del>                                     </del>	<del></del>			<del> </del>		<b></b>	<del> </del>	<del>                                     </del>	<del>}</del>	
	<del> </del>	<del>                                     </del>	<del></del>	-		<del></del>		<b></b>	<u> </u>	<del>                                     </del>	<del>                                     </del>		
	<u> </u>	<u> </u>	<u> </u>	1		<del>                                     </del>	f	<del></del> -		<b>†</b>			
	<del>                                     </del>	†	1							<b></b>	<del>                                     </del>		
, , , ,		†											
****			1	1									
TOTAL													
AVERAGE													
NOTES:	<del>-</del>		<del></del>					-					

Fig. 13—Data Summarization Form (Sheet 13 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

BUSY HOUR	
MONTH & YEAR	
	,

ENTITY						SREG MONTH & YEAR					YEAR	
0PM 007	SREG STUDY REG	ISTERS					0PM 007	SREG STUDY REG	ISTERS			
DATE	HOUR	DN/TG	PE LOCATION	PEG	USE	1	DATE	HOUR	DN/TG	PE LOCATION	PEG	USE
				-								
						1						
						1						
						1						
	<u> </u>					1						
	ļ					1						
	<u> </u>					1						
					***********	4						<u> </u>
						-{						
			1			1						
	-		-	******		4						
		ļ	-			1				-		
	ļ	<del> </del>	<del>  </del>			4				+		
	<del>                                     </del>	<u> </u>	<del>                                     </del>		ļ	1						
						1						
	1		<del>                                     </del>			1						
1	<u> </u>		<del>                                     </del>			1						
			+		1	1		<del></del>		· ·		<u> </u>
						1		1		1		
	<del>                                     </del>		<del>                                     </del>		<u> </u>	1			<u> </u>			
	1		†			1				f		
TOTAL						1				1		
AVERAGE	1					1						
NOTES:												

Fig. 13—Data Summarization Form (Sheet 14 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

ENTITY			DMS-1	O DAILY DATA RECO	ORD	BUSY HOUR _ MONTH & YEA	IR
OPM 009	ANI ANI CALLS	ANFL ANI FAILURE LOCAL OFC	ANFC ANI FAILURE CAMA OFC	ONI ONI CALLS	PDIS CAMA POS. DISCONNECTS	MCKF MATCH CHECK FAIL.	CLGF CALLING CODE FAIL.
DATE	PEG	PEG	PEG	PEG	PEG	PEG	PEG
TOTAL AVERAGE NOTES:							

Fig. 13—Data Summarization Form (Sheet 15 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

BUSY HOUR \_

# DMS-10 DAILY DATA RECORD OPM 010

ENTITY					HUNT GROU	JPS (HUNT)					
HTGP				HTGP				HTGP			
HUNT GROUP	NUMBER	<del></del>		HUNT GROUP	NUMBER	_		HUNT GROUP	NUMBER		
DATE	HOUR	PEG	OVFL	DATE	HOUR	PEG	OVFL	DATE	HOUR	PEG	OVFL
										<u> </u>	
		<u> </u>						<u> </u>	<b></b>	<u></u>	
		L								<u> </u>	
										<u> </u>	<u></u> _
			<b></b> _					<u> </u>	<u> </u>	<u> </u>	
		<b>↓</b>		<u> </u>	ļ	ļ		<b> </b>	ļ	<del> </del> -	
ļ			<del>                                     </del>	<u> </u>	<b></b>	<u> </u>			ļ		ļ
		<b>_</b>		<del> </del> -	<del> </del>					<u> </u>	
	-	<b>_</b>	<del> </del>	<del> </del>			<u> </u>	<del> </del>	<del>                                     </del>	<u> </u>	
			<del> </del>					<del> </del>			
<u> </u>	<del></del>	<del> </del>	<del>                                     </del>	<del> </del>	l		<del> </del>	<del>                                     </del>		<del> </del>	
			<del>                                     </del>	<del> </del> -			<u> </u>	<del> </del>		<del> </del>	
		<del> </del>			<del></del>	<del>"</del>				<del> </del>	
										1	
			<u></u>	<b></b>					<u></u>		
<u> </u>											
				<u> </u>						<u> </u>	
			<u></u>								
TOTAL	<del>-</del>		ļ	TOTAL				TOTAL		<b> </b>	
AVERAGE	L	ļ	<u> </u>	AVERAGE		L		AVERAGE	<u></u>	L	
NOTES:											

Fig. 13—Data Summarization Form (Sheet 16 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

### DMS-10 DAILY DATA RECORD

ENTITY\_\_\_\_\_ CUSTOM CALLING FEATURES BUSY HOUR \_\_\_\_\_\_

ENTITY\_\_\_\_\_ CUSTOM CALLING FEATURES MONTH & YEAR \_\_\_\_\_\_

ENITIT_						CUSIOM CALLING FEATURES			MUNIH & YEAR					
OPM 011	OPM CALL WAIT ATTEMPS		CALL FWD ACT	CALLS FORW	S Arded	SC LONG L Changes	SC SHORT L CHANGES	SPEED Long	CALLS LIST	SPEED SHORT	CALLS LIST	TH CA	REE WAY LLING	
	CWAT	CWAA	CFWA	CI	FWD	SCLL	SCSL	SI	PCL	SP	CS		3MC	
DATE	PEG	PEG	PEG	PEG	USE	PEG	PEG	PEG	USE	PEG	USE	PEG	BLK	USE
				<b>.</b>		ļ <u>.</u>								
					ļ	ļ			ļ					
									<b></b>			<u> </u>		
·				ļ		<u> </u>			<b>_</b>			<u> </u>		
						<del>                                     </del>						<del></del>	<u></u>	
				<del> </del>	<u> </u>									
	<u> </u>			<del> </del>	<del> </del>		i							
					<del></del>	<del> </del>						<del> </del> -		
					<del> </del>	<del> </del>			<del>                                     </del>			<del> </del>		
					-	<del> </del>						<u> </u>	-	<u> </u>
									<u> </u>					<del></del>
						<del> </del>								
			-											
								·						-
TOTAL														
AVERAGE					<u></u>					<u></u>				
NOTES:				!							1			

Fig. 13—Data Summarization Form (Sheet 17 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

BUSY HOUR \_\_\_\_

#### DMS-10 DAILY DATA RECORD DIVISION OF REVENUE MONTHLY PEG COINT

OPM 002 HOUR 0000		TOTAL OR:	TOTNATTN												
	TOTC - PEG						PERMA PSIG	GNAL		FALSE START FSTR – PEG					
0000	MON	TUES	WED	THUR	FRI	MON	TUES	WED	THUR	FRI	MON	TUES	WED	THUR	FRI
0000	·										ļ —			•	
0100															
0200															
0300												1			
0400						-			<u> </u>			İ			
0500															
0600											<del>†                                    </del>				
0700															
0800	****			<u> </u>	<del></del>				<u> </u>		<del>                                     </del>			<del>                                     </del>	
0900	·	<del>                                     </del>							<u> </u>						
1000					<u> </u>	1			<b>†</b>	<b></b>	† –	<u> </u>			
1100			<u> </u>										<u> </u>		
1200				1											
1300									†	$\vdash$					
1400	<del></del>	<del>                                     </del>	ļ		<del></del>				1	<u> </u>	<del>                                     </del>	1	<del>                                     </del>		
1500					<b>-</b>	i	<u></u>			l	1	<del>                                     </del>			
1600			<u> </u>	1	<del></del>	· · · · · · · · · · · · · · · · · · ·			<del> </del>	l	<del>                                     </del>				
1700			<u> </u>		<u> </u>	<del></del>			<del>                                     </del>		<del>                                     </del>				
1800	· ,-					<del>                                     </del>			1	<del>                                     </del>	<del>                                     </del>	<u> </u>			
1900											<del>                                     </del>				
2000					···-				<del>                                     </del>		<del>                                     </del>		<u> </u>		
2100			<del></del> -			· · · · · · · · · · · · · · · · · · ·			<u> </u>		<del></del>		<del>                                     </del>		
2200									<del> </del>		<del>}</del> _		<del>                                     </del>		
2300				<del>                                     </del>		<del></del>	$\vdash$				<del>                                     </del>	<del>                                     </del>	<del></del>	f	
TOTAL											<del>                                     </del>				
	TOTC _		L	L	L	PSIG _	·		<u> </u>	L	FSTR	L	L		
				s			S [PSIG P								

Fig. 13—Data Summarization Form (Sheet 18 of 18) (6.05, 6.07, 6.14, 6.17, 7.01, 8.02, 8.11)

Company Id: nnn

Monthly Report for mm/yyyy DMS10 Office Information as of mm/dd/yy TOTAL TOTAL TOTAL TOTAL REMOTE TOTAL LOCAL TOTAL NTWG LINES SCM LINES DCM REM х XXXX XXXX XXX XXX XXX OFFICE DIG ANA PBX MF DP TRKS TRKS TRKS TRKS TRKS TRKS XXXX XXXX XXXX XXXX XXXX XXXX OFFICE REMOTE LOCAL PBX COIN DP DGT MS MS MS MS MS MS MS xxxx xxxx XXXX XXXX xxxx XXXX XXXX Notes: TOTAL NTWG = number of network groups (max 3) TOTAL REMOTE LINES = total number of remote lines (this includes all lines connected to the office using a digital interface) TOTAL LOCAL LINES = total number of local analog lines (max ~6000) TOTAL DCM = number of digital carrier modules TOTAL REM = number of remote equipment modules TOTAL SCM = number of subscriber carrier modules OFFICE TRKS = number of trunks in the entire office = (DIG TRKS + ANA TRKS) = (MF TRKS + DP TRKS) DIG TRKS = number of digital trunks = number of analog trunks ANA TRKS PBX TRKS = number of PBX trunks MF TRKS = number of MF trunks DP TRKS = number of DP trunks OFFICE MS = number of main stations in the entire office = (DP MS + DGT MS)= (REMOTE MS + LOCAL MS + PBX MS + COIN MS) REMOTE MS = number of remote MS (this includes all MS connected to the office using a digital interface) LOCAL MS = number of local MS PBX MS = number of PBX MS COIN MS = number of coin MS DP MS = number of Dial Pulse MS DGT MS = number of Digitone MS

G. Issue

CLLIcode

nnnnnD10

Fig. 14—COER Output (Sheet 1 of 21) (8.07, 8.10)

nnnnnD10

CLLIcode

G.Issue

Company Id: nnn

DMS10 Office Totals Monthly Report for mm/yyyy Officewide Values

			O	RIG RI	ΕQ	INC REQ			
		O+I				ORIG		INC	
DATE	HOUR	CALLS	DP	DGT	TOTAL	CALLS	MF	CALLS	
		====							
mm/dd/yy*							xxxxx	xxxxx	
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	
•	•	•	•	•	•	•	•	•	
•	•	•	•	a	•	•	•	•	
•	•	•	•	•	•	•	•	•	
<b>AVERAGE</b> #		xxxxx	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	

Monthly Average stored in MLSS high-month results.

Notes: The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

#### Daily Calculations

```
OHI CALLS = ORIG CALLS + INC CALLS

ORIG PEO DE = ORIG PEO TOTAL ORIG PEO
```

ORIG REQ DP = ORIG REQ TOTAL - ORIG REQ DGT

ORIG REQ DGT = 5DGTRR ORIG REQ TOTAL = 5DIALR

ORIG CALLS = 1ORTMP + 1RVRTP + 1OROGP + 1ORNCP + 2PABNP

INC REQ MF = 5MFRR

INC CALLS = 1INTMP + 1INOGP + 1INNCP + 3PABNP

Fig. 14—COER Output (Sheet 2 of 21) (8.07, 8.10)

DMS10 Call Type Data Monthly Report for mm/yyyy Officewide Values

		O+1								
DATE	HOUR		ORIG	OUTGO		TANDEM			ORIG	INC
mm/dd/yy mm/dd/yy*	hh:mm hh:mm	xxxxx xxxxx	xxxxx xxxxx	xxxxx xxxxx	xxxxx xxxxx	xxxxx xxxxx	xxxxx	xxxxx	xxxxx xxxxx	
•	•	•	•	•	•	•	•	•	•	•
•	•	•	•	•	•	•	•	•	•	•
•	•	•	•	•	•	•	•	•	•	•
AVERAGE#		xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx

Monthly Average stored in MLSS high-month results.

Notes: The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

#### Daily Calculations

```
O+I CALLS
                      = ORIG CALLS + INC CALLS
ORIG CALLS
                      = 1ORTMP + 1RVRTP + 1OROGP + 1ORNCP + 2PABNP
INC CALLS
                      = 1INTMP + 1INOGP + 1INNCP + 3PABNP
TOTAL CALLS PC ORIG
                      = 1ORTMP + 1RVRTP + 1OROGP + 1ORNCP + 2PABNP
TOTAL CALLS PC OUTGO
                     = 10ROG(P+B) + 1INOG(P+B)
TOTAL CALLS PC IAO
                      = 1ORTM(P+B) + 1RVRTP
TOTAL CALLS PC TANDEM = 1INOG(P+B)
TOTAL CALLS PC INC
                      = 1INTMP + 1INOGP + 1INNCP + 3PABNP
TOTAL CALLS PC TERM
                      = 1ORTM(P+B) + 1INTM(P+B) + 1RVRTP
USAGE ORIG
                      = 1ORTMU + 1OROGU + 1RVRTU
USAGE INC
                      = 1INOGU + 1INTMU
```

Fig. 14—COER Output (Sheet 3 of 21) (8.07, 8.10)

nnnnnD10

CLLIcode

G. Issue

Company Id: nnn

DMS10 Attempts -- Originating Monthly Report for mm/yyyy Officewide Values

					_		PARTIA	AL DIAL	
DATE	HOUR	O+I CALLS	ORIG CALLS	INTCEP	FALSE				BLKED
DATE	1100K	CALLS	CALLS	CALLS	51AK15	SIGNAL	ABANDON	TIMEGUI	CALLS
			xxxxx		xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy*	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX
•	•	•	•	•	•	•	•	•	•
•	•	•	•	•	•	•	•	•	•
•	•	•	•	•	•	•	•	•	•
AVERAGE#		XXXXX	XXXXX	XXXXX	XXXXX	XXXXX	xxxxx	xxxxx	XXXXX

Monthly Average stored in MLSS high-month results.

Notes: The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

#### Daily Calculations

```
O+I CALLS
                     = ORIG CALLS + INC CALLS
                     = 1ORTMP + 1RVRTP + 1OROGP + 1ORNCP + 2PABNP
ORIG CALLS
INC CALLS
                     = 1INTMP + 1INOGP + 1INNCP + 3PABNP
INTCEP CALLS
                     = 1ORNCP - 2PDTOP - 1ORTMB - 1OROGB
FALSE STARTS
                     = 2FSTRP
PERM SIGNAL
                     = 2PSIGP
PARTIAL DIAL ABANDON = 2PABNP
PARTIAL DIAL TIMEOUT = 2PDTOP
BLKED CALLS
                     = 1ORTMB + 1OROGB
```

Fig. 14—COER Output (Sheet 4 of 21) (8.07, 8.10)

DMS10 Attempts -- Incoming Monthly Report for mm/yyyy Officewide Values

		0.7	TNC	TNTCPD			PARTIA	L DIAL	211122
		O+ I	INC	INTCEP		PERM			BLKED
DATE	HOUR	CALLS	CALLS	CALLS	HITS	SIGNAL	ABANDON	TIMEOUT	CALLS
		=====							
mm/dd/yy				xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy*	hh:mm	XXXXX	xxxxx	XXXXX	XXXXX	XXXXX	XXXXX	XXXXX	XXXXX
•	•	•	•	•	•	•	•	•	•
•	•	•	•	•	•	•	•	•	•
•	•	•	•	•	•	•	•	•	•
<b>AVERAGE</b> #		xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx

Monthly Average stored in MLSS high-month results.

Notes: The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

#### Daily Calculations

```
O+I CALLS
                     = ORIG CALLS + INC CALLS
ORIG CALLS
                     = 1ORTMP + 1RVRTP + 1OROGP + 1ORNCP + 2PABNP
INC CALLS
                     = 1INTMP + 1INOGP + 1INNCP + 3PABNP
INTCEP CALLS
                     = 1INNCP - 3PDTOP - 1INTMB - 1INOGB
                     = 3HITSP
HITS
PERM SIGNAL
                     = 3PSIGP
PARTIAL DIAL ABANDON = 3PABNP
PARTIAL DIAL TIMEOUT = 3PDTOP
BLKED CALLS
                     = 1INTMB + 1INOGB
```

Fig. 14—COER Output (Sheet 5 of 21) (8.07, 8.10)

nnnnnD10

CLLIcode

G. Issue

Company Id: nnn

#### DMS10 Conference Network Monthly Report for mm/yyyy Officewide Values

DATE	HOUR	PK-TRF USAGE	CCS /MS	MS	PEG CNT	HT SEC	BLK %	NCI	occ %
		*****							
mm/dd/yy mm/dd/yy*			XXXXX			XXXXX		XX XX	xx.x
min/ dd/ yy	1111 - 111111	*****	****	****	xxxxx	XXXXX	****	^^	^^.
•	•	•				•			•
•	•	•	•	•	•	•	•	•	•
•	•	•	•	•	•	•	•	•	•
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXXX	XXXXX	XXXXX	xx.x	XX	xx.x

#### EVHD Calculations:

	EVHD	EVHD	ADP	ADP	CURR	CAP	CAP	
DM	CCS	CCS/MS	CCS	CCS/MS	MS	CCS	%	
dd#	xxxxx	xxxxx	xxxxx	xxxxx	xxxx	XXXXX	xx.x	

EVHD values are stored in MLSS as high-month results.

Notes: The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

#### Daily Calculations

PK-TRF USAGE = SUM(6CONFnU) over all conference loops

CCS/MS = PK-TRF USAGE / MS

MS = ODF(Conference Circuits MS) at the time of data entry

PEG CNT = SUM(6CONFnP) over all conference loops

HT SEC = 100 \* PK-TRF USAGE / SUM(6CONFn(P-B)) over all conference loops

BLK % = 100 \* SUM(6CONFnB) over all conference loops / PEG CNT

NCI = ODF(Conference Circuits installed) at the time of data entry

OCC % = 100 \* PK-TRF USAGE / (36 \* NCI)

#### EVHD Calculations

EVHD CCS = ADP CCS + 2.6 \* standard deviation over month of

daily PK-TRF USAGE values

EVHD CCS/MS = EVHD CCS / CURR MS ADP CCS = AVERAGE(PK-TRF USAGE)

ADP CCS/MS = ADP CCS / CURR MS

CURR MS = ODF(Conference Circuits MS) at the time of report

CAP CCS = ODF(Conference Circuits engineered capacity CCS) at time of report

CAP % = 100 % EVHD CCS / CAP CCS

Fig. 14—COER Output (Sheet 6 of 21) (8.07, 8.10)

DMS10 Digitone Receivers Monthly Report for mm/yyyy Officewide Values

```
SRVC
                                                                          DIAL
                                                                L-L NTWK
                                                                          TONE
                PK-TRF
                        CCS
                                 DELAY DGT
                                               DGTR
                                                           OVF
                                                                 ML
                                                                    CCS
                                                                            BLK
 DATE
          HOUR
                 USAGE
                        /MS
                              MS
                                                                 %
                                                                    /LOOP
                                        CALLS
                                                PC
                                                     SEC
                                                            %
mm/dd/vv
                 XXXXX XXXXX XXX XX.X
         hh:mm
                                       XXXXX XXXXX XXXXX XX.X XXXX XX.X
mm/dd/yy* hh:mm
                 XXXXX XXXXX XXX XX.X
                                       XXXXX XXXXX XXXXX XX.X XX.X XXXXX XX.X
mm/dd/yy hh:mm xxxxx xxxxx xxx xx.x xxxxx xxxxx xxxxx xx.x xx.x xxxxx xx.x
EVHD Calculations:
                EVHD
                        EVHD
                                 ADP
                                                  CURR
                                                          CAP
                                                                  CAP
                                           ADP
        DM
                 CCS
                       CCS/MS
                                 CCS
                                         CCS/MS
                                                   MS
                                                          CCS
                                                                   %
                                                                         NCI
                ____
                        ____
                                ____
        dd#
                XXXXX
                        XXXXX
                                XXXXX
                                          XXXXX
                                                   XXX
                                                         xxxxx
                                                                 xx.x
                                                                         XXX
EVHD values stored in MLSS as high-month results.
Notes: The "*" flag indicates unreasonable or outlier data.
       The "#" flag marks a month with less than 15 unflagged days of data.
       The peak value column is underlined double ("===").
                         Daily Calculations
                   = 5DGTRU
PK-TRF USAGE
CCS/MS
                   = PK-TRF USAGE / MS
MS
                     ODF (number of Digitone Receiver MS) at time of data entry
DELAY %
                     2DGTS%
DGT CALLS
                     2DGTCP
DGTR PC
                     5DGTRP
HT SEC
                   = 100 * PK-TRF USAGE / 5DGTRP
                   = 100 * 5DGTRO / 5DGTR(P+O)
OVF %
                   = 100 * 1ORTMB / 1ORTM(P+B)
L-L ML %
SRVC NTWK CCS/LOOP = 5SNETU / ODF(number of service network loops)
DIAL TONE BLK %
                   = 100 \pm (5DIALR - 5DIALP) / 5DIALR
                          EVHD Calculations
EVHD CCS
            = ADP CCS + 2.6 * standard deviation over month of
                                       daily PK-TRF USAGE values
EVHD CCS/MS = EVHD CCS / CURR MS
ADP CCS
            = AVERAGE(PK-TRF USAGE)
ADP CCS/MS
            = ADP CCS / CURR MS
            = ODF(number of Digitone MS ) at the time of report
CURR MS
CAP CCS
            = ODF(Digitone Receiver engineered capacity CCS) at time of report
CAP %
            = 100 * EVHD CCS / CAP CCS
```

Fig. 14—COER Output (Sheet 7 of 21) (8.07, 8.10)

NCI

= ODF (Digitone Receiver circuits installed) at time of report

DMS10 MF Receivers Monthly Report for mm/yyyy Officewide Values

```
AVG CCS
                                                                       T-L
               PK-TRF
                        CCS
                               MF DELAY MFR
                                                           OVF /VOICE
                                               MFR
  DATE
          HOUR
                USAGE /MF TRK TRKS
                                     %
                                                                 LOOP
                                         CALLS
                                                 PC
                                                      SEC
                =====
mm/dd/yy hh:mm
                              xxx
                XXXXX
                       XXXXX
                                   XX.X
                                         XXXXX XXXXX XXXXX XX.X
                                                                XXXXX
                                                                       XX.X
mm/dd/yy* hh:mm
                XXXXX
                       XXXXX
                              XXX
                                         XXXXX XXXXX XXXXX XX.X
                                   XX.X
                                                                XXXXX
                                                                       XX.X
EVHD Calculations :
                        EVHD
                                      ADP
                                            ADP CCS
                                                     CURR
                EVHD
                       CCS/MF
                               ADP
                                    CCS/MF
                                            /VOICE
                                                     MF
                                                           CAP
                                                                 CAP
                                                                  %
       DM
                 CCS
                        TRK
                               CCS
                                      TRK
                                             LOOP
                                                     TRKS
                                                           CCS
                                                                       NCI
        dd#
                XXXXX
                       XXXXX
                              XXXXX
                                    XXXXX
                                           XXXXX
                                                     xxx
                                                           XXXXX
                                                                 XX.X
                                                                       XXX
EVHD values stored in MLSS as high-month results.
Notes: The "*" flag indicates unreasonable or outlier data.
      The "#" marks a month with less than 15 unflagged days of data.
       The peak value column is underlined double ("===").
                        Daily Calculations
PK-TRF USAGE
                  = 5MFRU
CCS/MF TRK
                  = PK-TRF USAGE / MF TRKS
MF TRKS
                  = ODF(number of MF trunks) at the time of data entry
                  = 3RDLY%
DELAY %
MFR CALLS
                  = 3MFRCP
MFR PC
                  = 5MFRP
HT SEC
                  = 100 * PK-TRF USAGE / 5MFRP
                  = 100 \div 5MFRO / 5MFR(P+O)
OVF %
AVG CCS/VOICE LOOP = SUM(6PCKTnU) over all voice loops
                      / ODF(number of voice MUX loops)
                  = 100 * 1INTMB / 1INTM(P+B)
T-L ML %
                         EVHD Calculations
                  = ADP CCS + 2.6 * standard deviation over month of
EVHD CCS
                                     daily PK-TRF USAGE values
EVHD CCS/MF TRK
                  = EVHD CCS / CURR MF TRKS
                  = AVERAGE(PK-TRF USAGE)
ADP CCS
                  = ADP CCS / CURR MF TRKS
ADP CCS/MF TRK
ADP CCS/VOICE LOOP = AVERAGE(AVG CCS/VOICE LOOP)
CURR MF TRKS
                  = ODF (number of MF trunks) at the time of report
CAP CCS
                  = ODF(MF Receiver engineered capacity CCS) at time of report
CAP %
                  = 100 * EVHD CCS / CAP CCS
NCI
            = ODF(number of MF Receiver circuits installed) at time of report
```

Fig. 14—COER Output (Sheet 8 of 21) (8.07, 8.10)

DMS10 Analog Shelves Monthly Report for mm/yyyy Officewide Values

```
PK-TRF
                                                                      % ML
                                        PEG CNT
                                                       HT SEC
                                ccs
                 NTWK
                          CCS
  DATE
                         /AMS
           HOUR
                 USAGE
                              /ATRK
                                       AMS
                                             ATRK
                                                           ATRK
                                                                 ORIG INC ANA
                                                     AMS
          ----
                  ----
                                      _____
                                                                 ____
mm/dd/yy hh:mm
                 XXXXX
                         XXXXX XXXXX
                                      XXXXX XXXXX
                                                                 xx.x xx.x xx.x
                                                    XXXXX XXXXX
mm/dd/yy* hh:mm
                  XXXXX
                         xxxxx xxxxx
                                      XXXXX XXXXX
                                                    XXXXX XXXXX
                                                                 XX.X XX.X XX.X
            .
                   .
                           .
                                 .
                                        .
                                              .
                                                      .
                                                            .
mm/dd/yy hh:mm
                 XXXXX
                        EVHD Calculations:
                  EVHD
                           EVHD
                                                                    ADP
                                                                            ANA
                                          EST
                                                     EST
                                                             ADP
                  NTWK
                           NTWK
                                  CURR
                                         SLAVE
                                                    SLAVE
                                                                    CCS
                                                                            MUX
                                                             CCS
        DM
                  CCS
                                                                           LOOPS
                         CCS/ELT
                                   ELT
                                        CCS/AMS
                                                  CCS/ATRK
                                                            /AMS
                                                                    /ATRK
        dd#
                  xxxxx
                          XXXXX
                                                                           XXXXX
                                  XXXX
                                         XXXXX
                                                    XXXXX
                                                            XXXXX
                                                                   XXXXX
EVHD values stored in MLSS as high-month results.
Notes: The "*" flag indicates unreasonable or outlier data.
       The "#" flag marks a month with less than 15 unflagged days of data. The peak value column is underlined double ("===").
                          Daily Calculations
PK-TRF NTWK USAGE = SUM(6PCKTnU) over all voice loops
CCS/AMS
                   = AMS USAGE /ODF(local MS) at the time of data entry
AMS USAGE
                  = SUM(6PCKTnU) over all analog shelves - ATRK USAGE
                   = ATRK USAGE / ODF(number of Analog Trunks) at time of data entry
CCS/ATRK
                  = SUM(4IGPiU + 4OGPiU) over all analog trunks
ATRK USAGE
PEG CNT AMS
                  = SUM(6PCKTnP) over all analog shelves - PEG CNT ATRK
                  = SUM(4IGPiP + 4OGPiP) over all analog trunks only
PEG CNT ATRK
                   = 100 * AMS USAGE / PEG CNT AMS
HT SEC AMS
                  = 100 * ATRK USAGE / PEG CNT ATRK
HT SEC ATRK
                  = 100 * (1INTMB + 1INOGB) / (1INTM(P+B) + 1INOG(P+B))
= 100 * (1ORTMB + 1OROGB) / (1ORTM(P+B) + 1OROG(P+B))
% ML INC
% ML ORIG
                   = 100 * (SUM(6PCKTnB) over all analog shelves)
% ML ANA
                         / (SUM(6PCKTn(P+B)) over all analog shelves)
                           EVHD Calculations
                     = AVERAGE(PK-TRF NTWK USAGE) + 2.6 \pm standard deviation
EVHD NTWK CCS
                         over month of daily PK-TRF NTWK USAGE values
                     = EVHD NTWK CCS / CURR ELT
EVHD NTWK CCS/ELT
CURR ELT
                     = (ODF(local MS) + ODF(analog TRK) * r1 + ODF(remote MS) * r2
                                 + ODF(digital TRK) * r3) at time of report
                     = ADP CCS/AMS * r
EST SLAVE CCS/AMS
EST SLAVE CCS/ATRK
                     = ADP CCS/ATRK * r
                     = AVERAGE(CCS/AMS)
ADP CCS/AMS
ADP CCS/ATRK
                     = AVERAGE(CCS/ATRK)
                     = ODF(number of analog mux loops) at time of report
ANA MUX LOOPS
     = EVHD NTWK CCS / AVERAGE(PK-TRF NTWK USAGE)
r
     = (EST SLAVE CCS/ATRK) / (EST SLAVE CCS/AMS)
r1
      = (EST SLAVE CCS/DMS) / (EST SLAVE CCS/AMS)
r2
     = (EST SLAVE CCS/DTRK) / (EST SLAVE CCS/AMS)
r3
```

Fig. 14—COER Output (Sheet 9 of 21) (8.07, 8.10)

#### DMS10 Digital Shelves Monthly Report for mm/yyyy Officewide Values

		PK-TRF			PEG	CNT	HT	SEC	% M	L
DATE	HOUR	NTWK USAGE	CCS /DMS	CCS /DTRK	DMS	DTRK	DMS	DTRK	INC ORI	G DIG
mm/dd/yy mm/dd/yy*		xxxxx		xxxxx	xxxxx	xxxxx		xxxxx	xx.x xx.	
•	•	•		•	•	•		•		•
•	•	•	•	•	•	•	•	•	•	•
• .	•	•	•	•		•	•	•		•
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x xx.	x xx.x
EVHD Calc	ulation	s:								
		EVHD	EVHI	)	E:	ST	EST	ADP	ADP	DIG
		NTWK	NTWI	K CUR	R SL	AVE	SLAVE	ccs	ccs	MUX
D:	М	CCS	CCS/E	LT ELT	CCS	/DMS	CCS/DTRI	K /DMS	/DTRK	LOOPS
-	 . //									
a	d#	XXXXX	XXXX	x xxx	x xx	XXX	XXXXX	XXXX	x xxxxx	xxxxx

EVHD values stored in MLSS as high-month results.

Notes: The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

#### Daily Calculations

```
PK-TRF NTWK USAGE = SUM(6PCKTnU) over all n voice loops
CCS/DMS

⇒ DMS USAGE / ODF(remote MS) at the time of data entry

DMS USAGE
              = SUM(6PCKTnU) over all digital shelves - DTRK USAGE
              = DTRK USAGE / ODF(number of Digital trunks) at time of data entry
CCS/DTRK
              = SUM(4IGPiU + 4OGPiU) over all digital trunks
DTRK USAGE
PEG CNT DMS = SUM(6PCKTnP) over all digital shelves - PEG CNT DTRK
PEG CNT DTRK = SUM(4IGPiP + 4OGPiP) over all digital trunks only
             = 100 * DMS USAGE / PEG CNT DMS
HT SEC DMS
HT SEC DTRK = 100 * DTRK USAGE / PEG CNT DTRK
             = 100 * (1INTMB + 1INOGB) / (1INTM(P+B) + 1INOG(P+B))
= 100 * (1ORTMB + 1OROGB) / (1ORTM(P+B) + 1OROG(P+B))
% ML INC
% ML ORIG
              = 100 * (SUM(6PCKTnB) over all digital shelves)
% ML DIG
                      / (SUM(6PCKTn(P+B)) over all digital shelves)
```

#### EVHD Calculations

```
= AVERAGE(PK-TRF NTWK USAGE) + 2.6 * standard deviation
EVHD NTWK CCS
                      over month of daily PK-TRF NTWK USAGE values
                  = EVHD NTWK CCS / CURR ELT
EVHD NTWK CCS/ELT
CURR ELT
                  = see calculation in B-9
EST SLAVE CCS/DMS = ADP CCS/DMS * r
EST SLAVE CCS/DTRK = ADP CCS/DTRK * r
ADP CCS/DMS
                   = AVERAGE(CCS/DMS)
ADP CCS/DTRK
                   = AVERAGE(CCS/DTRK)
DIG MUX LOOPS
                  = ODF(number of digital mux loops) at time of report
r = EVHD NTWK CCS / AVERAGE(PK-TRF NTWK USAGE)
```

Fig. 14—COER Output (Sheet 10 of 21) (8.07, 8.10)

DMS10 Processor -- Occupancy and Delay Peak Half-Hourly Data Monthly Report for mm/yyyy Officewide Values

```
PEAK
                                 MS
                                                 CALLS -- PC
                                                                    % DELAY
                  CPU
                        O+ I
                                         TRK
                                                                       DGT MF
  DATE
          HOUR
                 %OCC
                       CALLS
                              DP DGT
                                         MF
                                               DP
                                                     DGT MF
                                                                  DP
                 ====
                                                                 ____
                              ____
                                               _____
                                         ----
mm/dd/yy hh:mm xx.x
                             XXXX XXXX
                                               XXXXX XXXXX XXXXX XX.X XX.X
                      XXXXX
                                        XXXX
mm/dd/yy* hh:mm
                 xx.x
                       XXXXX
                              XXXX XXXX
                                        XXXX
                                               XXXXX XXXXX XXXXX XX.X XX.X
EVHD Calculations:
                                                     EVHD CPU USAGE (ms) per
                AVG
                       EVHD
                                             EVHD
                                                     _____
                CPU
                       CPU
                               CURR
                                      CURR
                                                     CURR
                                                             CURR
                                                                      EVHD
                                             O+I
                                                             ELT O+I CALLS
        DM
                %OCC
                       %OCC
                               MS
                                      ELT
                                             CALLS
                                                     MS
                       ____
                               ____
                                                     ____
                                                             ----
        dd#
                xx.x
                       xxx.x
                               XXXX
                                      XXXX
                                             XXXXX
                                                     XXXXX
                                                             XXXXX
                                                                     XXXXX
EVHD values stored in MLSS as high-month results.
Notes: The "^{*}" flag indicates unreasonable or outlier data.
       The "#" flag marks a month with less than 15 unflagged days of data.
       The peak value column is underlined double ("===").
PEAK CPU % OCC = 100 * (1 - (12BKGD/18))
O+I CALLS
               = ORIG CALLS + INC CALLS
ORIG CALLS
               = 1ORTMP + 1RVRTP + 1OROGP + 1ORNCP + 2PABNP
INC CALLS
               = 1INTMP + 1INOGP + 1INNCP + 3PABNP
               = ODF(DP MS) at the time of data entry.
MS DP
               = ODF(DGT MS) at the time of data entry.
MS DGT
TRK MF
                = ODF(MF trunks) at the time of data entry.
CALLS PC DP
               = 2DPCP
               = 2DGTCP
CALLS PC DGT
CALLS PC MF
               = 3MFRCP
% DELAY DP
               = 2DPS%
% DELAY DGT
               = 2DGTS%
                = 3RDLY%
% DELAY MF
                        EVHD Calculations
AVG CPU % OCC
                    = AVERAGE(PEAK CPU % OCC)
EVHD CPU % OCC
                    = AVERAGE(PEAK CPU % OCC) + 2.6 * standard deviation
                        over month of daily CPU % OCC values
CURR MS
                    = ODF(office MS) at time of report
CURR ELT
                    = value from B-9
EVHD O+I CALLS
                    = AVERAGE(O+I CALLS) + 2.6 * standard deviation
                        over month of daily O+I CALLS values
EVHD CPU USAGE
                    = EVHD CPU %OCC * 18000
EVHD CPU USAGE (ms) per CURR MS
EVHD CPU USAGE (ms) per CURR MS = EVHD CPU USAGE / CURR MS
EVHD CPU USAGE (ms) per CURR ELT = EVHD CPU USAGE / CURR ELT
EVHD CPU USAGE (ms) per EVHD O+I CALLS = EVHD CPU USAGE / EVHD O+I CALLS
                                      = EVHD CPU USAGE / CURR MS
```

Fig. 14—COER Output (Sheet 11 of 21) (8.07, 8.10)

nnnnnD10

CLLIcode

G.Issue

Company Id: nnn

DMS10 Office Totals
Traffic Machine Load and Service Summary
Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy
Officewide Values

High Days	:							
		O . T	OI	RIG RE	EQ	ODIC	INC REQ	TNC
DATE	HOUR	O+I CALLS	DP	DGT	TOTAL	ORIG CALLS	MF	INC CALLS
mm/dd/yy*	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	XXXXX
mm/dd/yy*	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	XXXXX
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
Monthly A	vgs:							
			0	ות סזר			THE DEC	
			O.	RIG R	EQ		INC REQ	
		O+ I				ORIG		INC
MONTH D		CALLS	DP	DGT	TOTAL	ORIG CALLS	MF	INC CALLS
	<del>-</del>	-	DP					
	_ d	CALLS	DP 	DGT	TOTAL	CALLS	MF	CALLS
mm/yy d	– d d	CALLS ===== xxxxx	DP 	DGT 	TOTAL  xxxxx xxxxx	CALLS 	MF 	CALLS  xxxxx
mm/yy d	– d d d	CALLS ===== xxxxx xxxxx	DP  xxxxx xxxxx xxxxx	DGT  xxxxx xxxxx	TOTAL  xxxxx xxxxx xxxxx	CALLS  XXXXX XXXXX	MF  xxxxx xxxxx	CALLS xxxxx xxxxx
mm/yy d mm/yy d mm/yy d	d d d d	CALLS ==== xxxx xxxx xxxx	DP  xxxxx xxxxx xxxxx	DGT  xxxxx xxxx xxxx	TOTAL xxxxx xxxxx xxxxx xxxxx	CALLS  xxxxx xxxxx xxxxx	MF  xxxxx xxxxx xxxxx	CALLS xxxxx xxxxx xxxxx
mm/yy d mm/yy d mm/yy d OFFICE 3H	d d d d	CALLS ====  xxxx  xxxx  xxxx  xxxx	DP	DGT xxxxx xxxxx xxxxx xxxxx xxxxx	TOTAL xxxxx xxxxx xxxxx xxxxx	CALLS xxxxx xxxxx xxxxx xxxxx	MF xxxxx xxxxx xxxxx xxxxx	CALLS xxxxx xxxxx xxxxx xxxxx
mm/yy d mm/yy d mm/yy d OFFICE 3H	d d d M	CALLS ====  xxxxx xxxxx xxxxx xxxxx xxxxx	DP	DGT xxxxx xxxxx xxxxx xxxxx	TOTAL xxxxx xxxxx xxxxx xxxxx	CALLS xxxxx xxxxx xxxxx xxxxx	MF	CALLS xxxxx xxxxx xxxxx
mm/yy d mm/yy d mm/yy d OFFICE 3H mm/yy d mm/yy d	d d d M d d	CALLS ====  xxxxx xxxxx xxxxx xxxxx xxxxx	DP	DGT xxxxx xxxxx xxxxx xxxxx	TOTAL xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	CALLS xxxxx xxxxx xxxxx xxxxx	MF	CALLS xxxxx xxxxx xxxxx xxxxx
mm/yy d mm/yy d mm/yy d OFFICE 3H mm/yy d mm/yy d mm/yy d mm/yy d	ddd dd M dd dd	CALLS ====  xxxx xxxx xxxx xxxx xxxx xxxx	DP xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	DGT xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	TOTAL xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	CALLS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	MF	CALLS xxxxx xxxxx xxxxx xxxxx xxxxx
mm/yy d mm/yy d mm/yy d OFFICE 3H mm/yy d mm/yy d mm/yy d mm/yy d mm/yy# d mm/yy d	- d d d M d d d d	CALLS ====  xxxx xxxx xxxx xxxx  xxxx xxxx	DP	DGT xxxxx xxxxx xxxxx xxxxx xxxx xxxx xxxx	TOTAL xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	CALLS XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX	MF xxxxx xxxxx xxxxx xxxxx xxxx xxxx xxxx	CALLS xxxxx xxxxx xxxxx xxxx xxx
mm/yy d mm/yy d mm/yy d OFFICE 3H mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d	- d d d d d d d d	CALLS ====  xxxx xxxx xxxx xxxx  xxxx xxxx	DP	DGT xxxxx xxxxx xxxxx xxxxx xxxx xxxx xxxx xxxx xxxx xxxx	TOTAL	CALLS XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX	MF xxxxx xxxxx xxxxx xxxxx xxxx xxxx xxxx xxxx xxxx xxxx	CALLS xxxxx xxxxx xxxxx xxxx xx
mm/yy d mm/yy d mm/yy d OFFICE 3H mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d	- d d d d d d d d	CALLS ====  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	DP xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	DGT xxxxx xxxxx xxxx xxxx xxxx xxxx	TOTAL	CALLS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	MF xxxxx xxxxx xxxx xxxx xxxx xxxx	CALLS xxxxx xxxxx xxxxx xxxxx xxxx xxxx xxxx xxxx xxxx xxxx xxxx
mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d	- d d d d d d d d d d	CALLS ====  XXXXX XXXXX XXXXX  XXXXX XXXXX XXXXX XXXX	DP xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	DGT xxxxx xxxxx xxxx xxxx xxxx xxxx	TOTAL xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	CALLS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx xxxxx xxxx	MF xxxxx xxxxx xxxx xxxx xxxx xxxx	CALLS xxxxx xxxxx xxxxx xxxxx xxxx xxxx xxxx xxxx xxxx xxxx xxxx

Notes: Ordering based on "O+I Calls."

The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 12 of 21) (8.07, 8.10)

nnnnnD10 CLLIcode G.Issue Company Id: nnn

DMS10 Processor -- Occupancy and Delay Peak Half-Hourly Data Monthly Report for mm/yyyy Officewide Values

```
PEAK
                           MS
                                          CALLS -- PC
                                                          % DELAY
              CPU
                    O+I
                                  TRK
                         _____
                                        _____
         HOUR
 DATE
              %OCC
                   CALLS
                         DP
                             DGT
                                   MF
                                        DP
                                             DGT
                                                  MF
                                                        DP
                                                             DGT MF
              ====
                   ____
                         ____
                                        _____
                                                        ____ ___
                                   ____
mm/dd/yy hh:mm xx.x xxxxx
                         XXXX XXXX
                                  XXXX
                                       XXXXX XXXXX XXXXX XX.X XX.X
mm/dd/yy* hh:mm xx.x
                   XXXXX
                         XXXX XXXX XXXX
                                       XXXXX XXXXX XXXXX XX.X XX.X
                              .
                                   .
                                         .
                                             .
                                                   .
EVHD Calculations:
                                             EVHD CPU USAGE (ms) per
             AVG
                   EVHD
                                      EVHD
                                             _____
             CPU
                   CPU
                          CURR
                                                    CURR
                                                           EVHD
                                CURR
                                             CURR
                                      O+ I
      DM
             %OCC
                   %OCC
                          MS
                                ELT
                                      CALLS
                                             MS
                                                    ELT O+I CALLS
             ____
                   ____
                          ____
                                _---
                                      ____
                                             ____
                                                    ____
                                                          ____
      dd#
             XX.X
                   XXX.X
                          XXXX
                                XXXX
                                      xxxxx
                                             XXXXX
                                                   XXXXX
                                                          XXXXX
EVHD values stored in MLSS as high-month results.
Notes: The "*" flag indicates unreasonable or outlier data.
     The "\#" flag marks a month with less than 15 unflagged days of data.
     The peak value column is underlined double ("===").
______
PEAK CPU % OCC = 100 * (1 - (12BKGD/18))
O+I CALLS
             = ORIG CALLS + INC CALLS
ORIG CALLS
             = 1ORTMP + 1RVRTP + 1OROGP + 1ORNCP + 2PABNP
             = 1INTMP + 1INOGP + 1INNCP + 3PABNP
INC CALLS
MS DP
             = ODF(DP MS) at the time of data entry.
             = ODF(DGT MS) at the time of data entry.
MS DGT
TRK MF
             = ODF(MF trunks) at the time of data entry.
CALLS PC DP
             = 2DPCP
             = 2DGTCP
CALLS PC DGT
CALLS PC MF
             = 3MFRCP
             = 2DPS%
% DELAY DP
% DELAY DGT
             = 2DGTS%
% DELAY MF
             = 3RDLY%
                    EVHD Calculations
```

```
AVG CPU % OCC
                    = AVERAGE(PEAK CPU % OCC)
                    = AVERAGE(PEAK CPU % OCC) + 2.6 * standard deviation
EVHD CPU % OCC
                        over month of daily CPU \% OCC values
                    = ODF(office MS) at time of report
CURR MS
CURR ELT
                    = value from B-9
EVHD O+I CALLS
                    = AVERAGE(O+I CALLS) + 2.6 * standard deviation
                        over month of daily O+I CALLS values
EVHD CPU USAGE
                    = EVHD CPU %OCC * 18000
EVHD CPU USAGE (ms) per CURR MS
                                      = EVHD CPU USAGE / CURR MS
                                      = EVHD CPU USAGE / CURR ELT
EVHD CPU USAGE (ms) per CURR ELT
EVHD CPU USAGE (ms) per EVHD O+I CALLS = EVHD CPU USAGE / EVHD O+I CALLS
```

Fig. 14—COER Output (Sheet 11 of 21) (8.07, 8.10)

CLLIcode

G.Issue

Company Id: nnn

DMS10 Office Totals Traffic Machine Load and Service Summary Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy Officewide Values

High Days	:							
			OF	RIG RE	EQ		INC REQ	
		O+I				ORIG		INC
DATE	HOUR	CALLS	DP	DGT	TOTAL	CALLS	MF	CALLS
		=====						
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	xxxxx	XXXXX	XXXXX	XXXXX
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	XXXXX	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	XXXXX	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	XXXXX	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	XXXXX	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXXXX	XXXXX	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	XXXXX	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	xxxxx	XXXXX	xxxxx	XXXXX	XXXXX	XXXXX	XXXXX
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	XXXXX	XXXXX	XXXXX	XXXXX
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	XXXXX	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	xxxxx	XXXXX	xxxxx	xxxxx	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	xxxxx	XXXXX	xxxxx	xxxxx	XXXXX	xxxxx	XXXXX
mm/dd/yy	hh:mm	xxxxx	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
Monthly A	Avgs:		0	סזר סו	FO		INC PEO	
Monthly A	Avgs:	O. I	O)	RIG R	EQ	ORIC	INC REQ	TNC
•		O+I				ORIG		INC
MONTH I	DM	CALLS	DP	RIG RI	EQ TOTAL	ORIG CALLS	INC REQ	INC CALLS
MONTH I	DM 	CALLS	DP	DGT	TOTAL	CALLS	MF	CALLS
MONTH I	DM  dd	CALLS ===== xxxxx	DP 	DGT 	TOTAL	CALLS  xxxxx	MF 	CALLS 
MONTH I	DM  dd dd	CALLS ===== xxxxx xxxxx	DP  xxxxx xxxxx	DGT  xxxxx xxxxx	TOTAL	CALLS  XXXXX XXXXX	MF  xxxxx xxxxx	CALLS
MONTH I	DM  dd	CALLS ===== xxxxx	DP 	DGT  xxxxx xxxxx	TOTAL	CALLS  xxxxx	MF 	CALLS xxxxx xxxxx
MONTH I	DM  dd dd dd	CALLS ===== xxxxx xxxxx	DP  xxxx xxxx xxxx	DGT  xxxxx xxxxx	TOTAL  xxxxx xxxxx xxxxx	CALLS  XXXXX XXXXX	MF  xxxxx xxxxx	CALLS xxxxx xxxxx
MONTH I	DM  dd dd dd	CALLS ===== xxxx xxxx xxxx	DP  xxxx xxxx xxxx	DGT  xxxx xxxx xxxx	TOTAL  xxxxx xxxxx xxxxx	CALLS XXXXX XXXXX	MF  xxxxx xxxxx xxxxx	CALLS xxxxx xxxxx xxxxx
MONTH II	DM  dd dd dd	CALLS ===== xxxx xxxx xxxx	DP xxxxx xxxxx xxxxx xxxxx	DGT  xxxx xxxx xxxx	TOTAL xxxxx xxxxx xxxxx xxxxx	CALLS XXXXX XXXXX	MF  xxxxx xxxxx xxxxx	CALLS xxxxx xxxxx xxxxx
MONTH II II mm/yy II mm/yy II OFFICE 3I mm/yy II	DM  dd dd dd	CALLS ====  XXXX  XXXX  XXXX  XXXX	DP xxxxx xxxxx xxxxx xxxxx	DGT xxxxx xxxxx xxxxx xxxxx xxxxx	TOTAL  XXXXX  XXXXX  XXXXX  XXXXX	CALLS xxxxx xxxxx xxxxx xxxxx	MF  xxxxx xxxxx xxxxx xxxxx	CALLS xxxxx xxxxx xxxxx xxxxx
MONTH II mm/yy omm/yy of OFFICE 3I mm/yy of mm/yy of	DM  dd dd dd HM	CALLS ====  xxxx xxxx xxxx xxxx xxxx	DP xxxxx xxxxx xxxxx xxxxx	DGT	TOTAL  XXXXX  XXXXX  XXXXX  XXXXX	XXXXX XXXXX XXXXX XXXXX XXXXX	MF	CALLS xxxxx xxxxx xxxxx xxxxx
MONTH II II mm/yy (II mm/yy) (II mm	DM  dd dd dd HM dd	CALLS ====  XXXX XXXX XXXX  XXXX  XXXXX	DP	DGT	TOTAL  XXXXX  XXXXX  XXXXX  XXXXX  XXXXX  XXXX	XXXXX XXXXX XXXXX XXXXX XXXXX	MF	CALLS xxxxx xxxxx xxxxx xxxxx
MONTH II mm/yy o mm/yy o OFFICE 3H mm/yy o mm/yy o mm/yy o mm/yy o mm/yy o mm/yy o	DM  dd dd dd HM dd dd	CALLS ====  XXXX XXXX XXXX  XXXX  XXXX  XXXX XXXX	DP xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	DGT	TOTAL  XXXXX  XXXXX  XXXXX  XXXXX  XXXXX  XXXX	CALLS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	MF xxxxx xxxxx xxxxx xxxxx	CALLS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx
MONTH II mm/yy o mm/yy o OFFICE 3H mm/yy o mm/yy o mm/yy o mm/yy o mm/yy o mm/yy o mm/yy o	DM  dd dd dd dd dd dd dd	CALLS ====  XXXX XXXX XXXX  XXXX  XXXX  XXXX XXXX XXXX	DP xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	DGT	TOTAL  XXXXX  XXXXX  XXXXX  XXXXX  XXXXX  XXXX	CALLS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	MF xxxxx xxxxx xxxxx xxxxx xxxx xxxx xxxx	CALLS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx
MONTH II II mm/yy II mm/yy II OFFICE 3I mm/yy II mm/	DM  dd dd dd dd dd dd dd	CALLS ====  XXXX XXXX XXXX  XXXX  XXXX XXXX	DP xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	DGT	TOTAL  XXXXX  XXXXX  XXXXX  XXXXX  XXXXX  XXXX	XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	MF xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	CALLS xxxxx xxxxx xxxxx xxxxx xxxx xxxx xxxx xxxx xxxx
MONTH II II mm/yy II mm/yy II OFFICE 3H mm/yy II mm/	DM dd dd dd dd dd dd dd dd	CALLS  ====  XXXXX  XXXXX  XXXXX  XXXXX  XXXXX  XXXX	DP xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	DGT xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	TOTAL xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	MF xxxx xxxx xxxx xxxx xxxx xxxx xx	CALLS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx xxxxx xxxx
MONTH II  mm/yy of	DM dd dd dd dd dd dd dd dd dd	CALLS  ====  XXXXX  XXXXX  XXXXX  XXXXX  XXXXX  XXXX	DP xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	DGT xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	TOTAL xxxxx xxxxx xxxxx xxxxx xxxxx xxxx xxxx	CALLS  XXXXX  XXXXX  XXXXX  XXXXX  XXXXX  XXXXX  XXXXX  XXXX	MF xxxxx xxxxx xxxxx xxxx xxxx xxxx	CALLS xxxxx xxxxx xxxxx  xxxxx xxxx xxxx xxxx xxxx xxxx xxxx

Notes: Ordering based on "O+I Calls."

The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 12 of 21) (8.07, 8.10)

CLLIcode

G.Issue

Company Id: nnn

DMS10 Call Type Data Traffic Machine Load and Service Summary Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy Officewide Values

	:	0.7		TO	TAL CAI	LLS I	PC .		USA	AGE
DATE	HOUR	O+I CALLS	ORIG	OUTGO	IAO	TANDEM	INC	TERM	ORIG	INC
num/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy*	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxx	xxxxx	xxxxx
nm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
nm/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
nm/dd/yy	hh:mm	xxxxx	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxx
nm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx
nm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy*	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xxxxx	XXXXX	xxxxx
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xxxxx	XXXXX	XXXXX
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	XXXXX
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	XXXXX
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXXXX	xxxxx	XXXXX	xxxxx	xxxxx	XXXXX	XXXXX
Monthly A				TΩ	TAI. CAI	LLS 1	PC.		USU	AGE
				TO	TAL CAI	LLS 1	PC		USA	AGE
Monthly A		O+I CALLS	ORIG	TO	IAL CAI	LLS I	PC INC	 TERM	USA	AGE  INC
Monthly A	vgs: M	O+I CALLS			IAO	TANDEM	INC	TERM		INC
Monthly A  MONTH D   mm/yy d	vgs: M - d	O+I CALLS	xxxxx	OUTGO	IAO  xxxxx	TANDEM	INC	xxxxx	ORIG	INC 
Monthly A  MONTH D   mm/yy d	vgs: M - d	O+I CALLS ===== xxxxx	xxxxx xxxxx xxxxx	OUTGO  xxxxx xxxxx xxxxx	IAO  xxxxx xxxxx xxxxx	TANDEM xxxxx xxxxx	INC 	xxxxx xxxxx	ORIG  xxxxx xxxxx	INC  xxxxx xxxxx
Monthly A  MONTH D   mm/yy d  mm/yy d	vgs: M - d d d	O+I CALLS ==== xxxxx xxxxx	*******  *******  *******	OUTGO  xxxxx xxxxx	IAO  xxxxx xxxxx xxxxx	TANDEM xxxxx xxxxx	INC  xxxxx xxxxx	xxxx xxxxx xxxxx	ORIG  xxxxx xxxxx	INC XXXXX XXXXX
Monthly A  MONTH D   mm/yy d  mm/yy d  mm/yy d	vgs: M - d d d	O+I CALLS ===== xxxxx xxxxx xxxxx	xxxx xxxx xxxx xxxx	OUTGO  xxxxx xxxxx xxxxx	IAO  xxxxx xxxxx xxxxx  xxxxx	TANDEM xxxxx xxxxx xxxxx xxxxx	INC  xxxxx xxxx xxxx	xxxxx xxxxx xxxxx xxxxx	ORIG  xxxxx xxxxx xxxxx	INC  xxxxx xxxxx xxxxx
Monthly A  MONTH D  mm/yy d  mm/yy d  mm/yy d  mm/yy d	vgs: M - d d d	O+I CALLS ===== xxxxx xxxxx xxxxx xxxxx	******  ******  ******  ******  ******	OUTGO  xxxxx xxxxx xxxxx xxxxx	IAO xxxxx xxxxx xxxxx xxxxx	TANDEM xxxxx xxxxx xxxxx xxxxx	INC  xxxxx xxxxx xxxxx  xxxxx	xxxxx xxxxx xxxxx xxxxx xxxxx	ORIG  XXXXX XXXXX XXXXX XXXXX	INC XXXXX XXXXX XXXXX XXXXX
Monthly A  MONTH D  mm/yy d  mm/yy d  mm/yy d  operated 3H  mm/yy d  mm/yy d	vgs: M - d d d	O+I CALLS ==== xxxxx xxxxx xxxxx xxxxx	******  ******  ******  ******	OUTGO  xxxxx xxxxx xxxxx  xxxxx	IAO xxxxx xxxxx xxxxx xxxxx	TANDEM xxxxx xxxxx xxxxx xxxxx xxxxx	INC XXXXX XXXXX XXXXX XXXXX	xxxx xxxx xxxx xxxx xxxx xxxx	ORIG XXXXX XXXXX XXXXX XXXXX	INC XXXXX XXXXX XXXXX XXXXX XXXXX
Monthly A  MONTH D  mm/yy d  mm/yy d  mm/yy d  OFFICE 3H  mm/yy d  mm/yy d  mm/yy d  mm/yy d	vgs:  M - d d d d	O+I CALLS ===== xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	******  ******  ******  ******  ******  ****	OUTGO xxxxx xxxxx xxxxx xxxxx	IAO xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	TANDEM xxxxx xxxxx xxxxx xxxxx xxxxx	INC XXXXX XXXXX XXXXX XXXXX	xxxx xxxx xxxx xxxx xxxx xxxx xxxx xxxx	ORIG XXXXX XXXXX XXXXX XXXXX	INC XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX
MONTH D mm/yy d mm/yy d OFFICE 3H mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d	vgs:  M - d d d d	O+I CALLS ===== xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	******  ******  ******  ******  ******  ****	OUTGO xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	IAO xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	TANDEM XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	INC XXXXX XXXXX XXXXX XXXXX XXXXX	xxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	ORIG XXXXX XXXXX XXXXX XXXXX	INC
MONTH D mm/yy d mm/yy d oFFICE 3H mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d	vgs:  M d d d d	O+I CALLS ===== xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	******  ******  ******  ******  ******  ****	OUTGO xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	IAO xxxxx xxxxx xxxxx xxxxx xxxxx xxxx xxxxx xxxxx xxxxx	TANDEM XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	INC xxxxx xxxxx xxxx xxxxx xxxx xxxx xxxx	xxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	ORIG XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX	INC
Monthly A  MONTH D   mm/yy d  mm/yy d  OFFICE 3H  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d	vgs:  M d d d d d	O+I CALLS ===== xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	******  ******  ******  ******  ******  ****	OUTGO xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	IAO xxxxx xxxxx xxxx xxxx xxxx xxxx	TANDEM xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	INC xxxxx xxxxx xxxx xxxxx xxxx xxxx xxxx xxxx xxxx	xxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	ORIG XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX	INC
Monthly A  MONTH D  mm/yy d	vgs:  M d d d d d d	O+I CALLS ===== xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	******  ******  ******  *****  *****  ****	OUTGO xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	IAO xxxxx xxxxx xxxx xxxx xxxx xxxx	TANDEM xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	INC XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	ORIG XXXX XXXX XXXX XXXX XXXX XX	INC XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX

Notes: Ordering based on "O+I Calls."

The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 13 of 21) (8.07, 8.10)

CLLIcode

G.Issue

Company Id: nnn

DMS10 Attempts -- Originating Traffic Machine Load and Service Summary Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy Officewide Values

_		O 7	ODIC	THEORE	B	DEDM	1711(111	L DIAL	BLKE
DATE	HOUR	O+I CALLS	ORIG CALLS	INTCEP CALLS	FALSE STARTS	PERM SIGNAL	ABANDON	TIMEOUT	CALL
m/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxx	xxxx	xxxxx	xxxxx	xxxx
m/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxx	XXXXX	XXXXX	XXXXX	XXXX
m/dd/yy	hh:mm	xxxxx	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXX
m/dd/yy	hh:mm	xxxxx	xxxxx	XXXXX	XXXXX	XXXXX	xxxxx	XXXXX	XXXX
m/dd/yy	hh:mm	xxxxx	xxxxx	XXXXX	xxxxx	XXXXX	XXXXX	XXXXX	XXX
m/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	XXXXX	XXX
m/dd/yy	* hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	XXXXX	XXX
m/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	xxxxx	XXXXX	xxxxx	xxxxx	XXX
m/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	XXXXX	XXXXX	XXXXX	xxxxx	XXX
m/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	XXXXX	XXXXX	xxxxx	xxxxx	XXX
m/dd/yy	hh:mm	xxxxx	XXXXX	XXXXX	xxxxx	XXXXX	XXXXX	xxxxx	XXX
m/dd/yy	hh:mm	xxxxx	XXXXX	xxxxx	xxxxx	XXXXX	xxxxx	xxxxx	XXX
m/dd/yy	hh:mm	xxxxx	XXXXX	xxxxx	xxxxx	XXXXX	xxxxx	xxxxx	XXX
m/dd/yy	hh:mm	xxxxx	xxxxx	XXXXX	XXXXX	XXXXX	XXXXX	XXXXX	XXX
mm/dd/yy Monthly		xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxx
nm/dd/yy Monthly								AL DIAL	
onthly .	Avgs:	O+I	ORIG	INTCEP	FALSE	PERM	PARTI	AL DIAL	BLK
Nonthly							PARTI		
ONTH	Avgs:	O+I CALLS	ORIG	INTCEP	FALSE	PERM SIGNAL	PARTI	AL DIAL	BLK CAL
ONTH	Avgs: DM	O+I CALLS	ORIG CALLS	INTCEP CALLS	FALSE STARTS	PERM SIGNAL	PARTIA ABANDON	AL DIAL TIMEOUT	BLK CAL 
ONTH : m/yy m/yy	Avgs: DM  dd	O+I CALLS ==== xxxxx xxxxx xxxxx	ORIG CALLS  xxxx xxxx xxxx	INTCEP CALLS  xxxxx	FALSE STARTS  xxxxx xxxxx xxxxx	PERM SIGNAL  xxxxx xxxxx	PARTIA ABANDON xxxxx xxxxx	AL DIAL TIMEOUT xxxxx xxxxx xxxx	BLK CAL  XXX XXX
ONTH IONTH Im/yy Im/yy Im/yy Im/yy	Avgs: DM  dd dd dd	O+I CALLS ==== xxxxx xxxx	ORIG CALLS  xxxxx xxxxx	INTCEP CALLS  xxxxx xxxxx	FALSE STARTS  XXXXX XXXXX	PERM SIGNAL  xxxxx xxxxx	PARTIA ABANDON xxxxx xxxx	AL DIAL TIMEOUT xxxxx xxxxx	BLK
MONTH  MONTH  Myy  Myy  Myy  Myy  Myy  Myy  Morrice 3	Avgs: DM  dd dd dd	O+I CALLS ==== xxxxx xxxx xxxx	ORIG CALLS  xxxxx xxxxx xxxxx	INTCEP CALLS  xxxxx xxxxx xxxxx	FALSE STARTS  XXXXX XXXXX XXXXX	PERM SIGNAL  xxxxx xxxxx xxxxx	PARTIA ABANDON xxxxx xxxxx	AL DIAL TIMEOUT xxxxx xxxxx xxxxx	BLK CAL  xxx xxx xxx
ionthly indicated in the control of	Avgs:  DM   dd  dd  dd	O+I CALLS ==== xxxxx xxxxx xxxxx  xxxxx	ORIG CALLS  xxxxx xxxxx xxxxx  xxxxx	INTCEP CALLS  xxxxx xxxxx xxxxx  xxxxx	FALSE STARTS  xxxxx xxxxx xxxxx xxxxx xxxxx	PERM SIGNAL  xxxxx xxxxx xxxxx xxxxx	PARTIA ABANDON xxxxx xxxxx xxxxx xxxxx	AL DIAL TIMEOUT xxxxx xxxxx xxxxx xxxxx	BLK CAL  xxx xxx xxx xxx
CONTH  IONTH  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy	Avgs:  DM   dd  dd  dd  dd	O+I CALLS ==== xxxxx xxxxx xxxxx xxxxx xxxxx	ORIG CALLS  xxxxx xxxxx xxxxx  xxxxx	INTCEP CALLS  xxxxx xxxxx xxxxx  xxxxx	FALSE STARTS  XXXXX XXXXX XXXXX  XXXXX	PERM SIGNAL  xxxxx xxxxx xxxxx xxxxx  xxxxx	PARTIA ABANDON XXXXX XXXXX XXXXX XXXXX XXXXX	AL DIAL TIMEOUT xxxxx xxxxx xxxxx xxxxx	BLK CAL  xxx xxx xxx  xxx
ONTH  IONTH  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy	Avgs:  DM   dd  dd  dd  dd  dd	O+I CALLS ====  xxxxx xxxxx xxxxx xxxxx xxxxx	ORIG CALLS  xxxxx xxxxx xxxxx  xxxxx	INTCEP CALLS  xxxxx xxxxx xxxxx  xxxxx	FALSE STARTS  XXXXX XXXXX XXXXX  XXXXX	PERM SIGNAL  xxxxx xxxxx xxxxx  xxxxx	PARTIA ABANDON xxxxx xxxxx xxxxx xxxxx xxxxx	AL DIAL TIMEOUT xxxxx xxxxx xxxxx xxxxx xxxxx	BLK CAL  xxx xxx xxx xxx xxx xxx
ONTH  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy  IM/yy	Avgs:  DM  dd dd dd dd dd dd	O+I CALLS ===== XXXX XXXX XXXX XXXX XXXX XXXX	ORIG CALLS  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX	INTCEP CALLS  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX	FALSE STARTS  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX	PERM SIGNAL  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX	PARTIA ABANDON XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	AL DIAL TIMEOUT XXXX XXXX XXXX XXXX XXXX XXXX XXXX	BLK CAL  xxx xxx xxx xxx xxx xxx xxx
ONTH  IONTH  IM/yy	Avgs:  DM   dd  dd  dd  dd  dd  dd	O+I CALLS XXXX XXXX XXXX XXXX XXXXX XXXX XXXX XXXX	ORIG CALLS  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	INTCEP CALLS XXXX XXXX XXXX XXXX XXXX XXXX X	FALSE STARTS  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	PERM SIGNAL  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	PARTIA ABANDON XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	AL DIAL TIMEOUT XXXX XXXX XXXX XXXX XXXX XXXX XXXX X	BLK CAL  xxx xxx xxx xxx xxx xxx xxx xxx
ONTH  ONTH  m/yy  m/yy  FFICE 3  m/yy  m/yy  m/yy  m/yy  m/yy  m/yy  m/yy  m/yy  m/yy  m/yy  m/yy	Avgs:  DM   dd  dd  dd  dd  dd  dd  dd  dd	O+I CALLS xxxx xxxx xxxx xxxx xxxx xxxx x	ORIG CALLS  xxxx xxxx xxxx xxxx xxxx xxxx x	INTCEP CALLS XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	FALSE STARTS  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	PERM SIGNAL  xxxxx xxxxx xxxxx  xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	PARTIA  ABANDON  XXXX  XXXX  XXXX  XXXX  XXXX  XXXX  XXXX	AL DIAL TIMEOUT XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	BLK CAL  xxx xxx xxx xxx xxx xxx xxx xxx xx
IONTH IONTH IONTH IONTH ION/YY ION/YY ION/YY ION/YY ION/YY ION/YY ION/YY ION/YY ION/YY ION/YY ION/YY ION/YY ION/YY ION/YY	Avgs:  DM   dd  dd  dd  dd  dd  dd  dd  dd  d	O+I CALLS ===== xxxxx xxxx xxxx xxxx xxxx xxxx	ORIG CALLS  xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	INTCEP CALLS XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	FALSE STARTS  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	PERM SIGNAL  xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	PARTIA  ABANDON  XXXX  XXXX  XXXX  XXXX  XXXX  XXXX  XXXX	AL DIAL TIMEOUT XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	BLK CAL  xxx xxx xxx xxx xxx

Notes: Ordering based on "O+I Calls."

The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 14 of 21) (8.07, 8.10)

CLLIcode

G.Issue

Company Id: nnn

DMS10 Attempts -- Incoming Traffic Machine Load and Service Summary Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy Officewide Values

		O+I	INC	INTCEP		PERM	PARTI	AL DIAL
DATE	HOUR	CALLS	CALLS	CALLS	HITS	SIGNAL		TIMEOUT
mm/dd/yy	hh:mm	xxxxx	xxxxx	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy*	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy*	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
Monthly Av	/gs:	O+ I	ORIG	INTCEP		PERM	PARTI	AL DIAL
MONTH DI		CALLS	CALLS	CALLS	HITS	SIGNAL	ABANDON	TIMEOUT
mm/yy do		xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
num/yy do	i	xxxxx	XXXXX	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx
nm/yy do	3	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
OFFICE 3H	1	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
mun/yy do	i	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
nnn/yy do	i	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
nm/yy do	i	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
nm/yy do	i	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
, .	1	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
	1	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx
	1							
mm/yy do mm/yy do	_	xxxxx	XXXXX	XXXXX	XXXXX	XXXXX	XXXXX	XXXXX
mm/yy do	i		XXXXX XXXXX	XXXXX XXXXX	XXXXX XXXXX	XXXXX XXXXX	xxxxx xxxxx	xxxxx xxxxx

Notes: Ordering based on "O+I Calls."

The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data. The peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 15 of 21) (8.07, 8.10)

CLLIcode

G. Issue

Company Id: nnn

DMS10 Conference Network Traffic Machine Load and Service Summary Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy Officewide Values

High Day	s:								
_		PK-TRF	ÇCS		PEG	HT	BLK		occ
DATE	HOUR	USAGE	/MS	MS	CNT	SEC	%	NCI	%
mm/dd/yy	hh:mm								
mm/dd/yy		XXXXX	XXXXX	XXXX	XXXXX	XXXXX	XXXXX	XX	xx.x
mm/dd/yy		XXXXX	XXXXX	XXXX	XXXXX	xxxxx	XXXXX	xx	xx.x
mm/dd/yy		XXXXX	XXXXX	XXXX	XXXXX	XXXXX	XXXXX	xx	xx.x
mm/dd/yy		XXXXX	XXXXX	XXXX	XXXXX	xxxxx	XXXXX	ХX	xx.x
mm/dd/yy		XXXXX	XXXXX	XXXX	XXXXX	XXXXX	XXXXX	XX	xx.x
		XXXXX	XXXXX	XXXX	XXXXX	XXXXX	xxxxx	ХX	xx.x
mm/dd/yy		XXXXX	XXXXX	XXXX	XXXXX	xxxxx	XXXXX	ХX	xx.x
mm/dd/yy		XXXXX	XXXXX	XXXX	XXXXX	XXXXX	XXXXX	XX	xx.x
mm/dd/yy		XXXXX	XXXXX	xxxx	XXXXX	XXXXX	XXXXX	ХX	xx.x
mm/dd/yy		XXXXX	XXXXX	xxxx	XXXXX	XXXXX	XXXXX	ХX	xx.x
mm/dd/yy		XXXXX	XXXXX	XXXX	XXXXX	xxxxx	XXXXX	ХX	xx.x
mm/dd/yy		XXXXX	XXXXX	XXXX	XXXXX	xxxxx	XXXXX	XX	XX.X
mm/dd/yy		XXXXX	XXXXX	XXXX	XXXXX	XXXXX	XXXXX	xx	xx.x
mm/dd/yy		xxxxx	XXXXX	XXXX	XXXXX	XXXXX	xxxxx	XX	xx.x
mm/dd/yy	hh:mm	xxxxx	XXXXX	XXXX	XXXXX	XXXXX	XXXXX	XX	XX.X
Monthly	EVHD's:								
,	_	EVHD	EVHD	ADP	AD	P C	URR (	CAP	CAP
MONTH	DM	CCS	CCS/MS	CCS	CCS			CCS	%
	dd	xxxxx	xxxxx	xxxxx	xxx	xx x	xxx x	xxxx	xx.x
	dd	xxxxx	XXXXX	XXXXX	xxx.	XX X	xxx x	xxxx	xx.x
mm/yy	dd	xxxxx	xxxxx	XXXXX	xxx	xx x	xxx x	xxxx	xx.x
OFFICE 3	HM	xxxxx	xxxxx	xxxxx	xxx	xx x	xxx x	xxxx	xx.x
	dd	xxxx	xxxxx	xxxxx	xxx	xx x	xxx x	xxxx	xx.x
.* *	dd	XXXXX	XXXXX	XXXXX	xxx:	XX X	xxx x	XXXX	xx.x
mm/yy	dd	XXXXX	XXXXX	XXXXX	xxx:	xx x	xxx x	XXXX	xx.x
	dd	xxxxx	XXXXX	XXXXX	xxx:	xx x	xxx x	xxxx	xx.x
mm/yy#	dd	xxxxx	XXXXX	XXXXX	xxx:	xx x	xxx x	xxxx	xx.x
	dd	xxxxx	xxxxx	xxxxx	xxx	xx x	xxx x	xxxx	xx.x
	dd	xxxxx	xxxxx	XXXXX	xxx	xx x	xxx x	xxxx	xx.x
mm/yy	dd	xxxxx	xxxxx	xxxxx	xxx	xx x	xxx x	xxxx	xx.x
mm/yy	dd	xxxxx	xxxxx	xxxxx	xxx	xx x	xxx x	xxxx	xx.x

Notes: Ordering based on "PK-TRF USAGE" for high days, "EVHD CCS/MS" for monthly EVHD's.

The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data. The peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 16 of 21) (8.07, 8.10)

CLLIcode

G. Issue

Company Id: nnn

DMS10 Digitone Receivers
Traffic Machine Load and Service Summary
Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy
Officewide Values

High Day	s:											
											SRVC	DIA
										L-L	NTWK	TONE
		PK-TR			DELAY	DGT	DGTR			ML	CCS	BLI
DATE	HOUR	USAGE	/MS	MS	%	CALLS	PC	SEC	%	%	/LOOP	%
mm/dd/yy	hh:mm		xxxxx	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	хх.х	xxxxx	xx.:
mm/dd/yy	* hh:mm	XXXXX	xxxxx	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xxxxx	xx.
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xxxxx	xx.
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xxxxx	xx.
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xxxxx	xx.
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xxxxx	XX.
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxx	xx.x	XXXXX	xxxxx	xxxxx	xx.x	xx.x	xxxxx	xx.
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xxxxx	xx.
mm/dd/yy	* hh:mm	XXXXX	xxxxx	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xxxxx	xx.
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	XXXXX	XX.
mm/dd/yy		XXXXX	xxxxx	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xxxxx	xx.
mm/dd/yy		XXXXX	XXXXX	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	XXXXX	xx.
mm/dd/yy		XXXXX	XXXXX	xxx	xx.x	XXXXX	xxxxx	xxxxx	xx.x	xx.x	xxxxx	xx.
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxx	xx.x	XXXXX	xxxxx	XXXXX	XX.X	xx.x	XXXXX	XX.
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xxxxx	xx.
Monthly	EVHD's:											
J		EVHD	EVHD		ADP	ADP	CUI	RR C	AP	CAP		
		ccs	CCS/MS		CCS	CCS/MS			CS		NCI	
	 dd	xxxxx	xxxxx		xxxxx	XXXXX	x xx		 xxx	 xx.x	xxx	
	dd	xxxxx	xxxxx	ζ.	xxxx	XXXXX		x xx	xxx	xx.x	xxx	
, , ,	dd	VVVVV	****	,	vvvv	***		v vv	vvv	VV V	***	

mm/yy dd XXXXX XXXXX XXXXX XXXXX XXX XXXXX XX.X xxx\_\_\_\_ ----OFFICE 3HM XXXXX XXXXX XXXXX XXXXX xxxXXXXX xx.x xxx mm/yy XXXXX XXXXX XXXXX XXXXX  $\mathbf{x}\mathbf{x}\mathbf{x}$ XXXXX xx.x xxxmm/yy dd XXXXX XXXXX XXXXX XXXXX xxxXXXXX XX.X XXX mm/yy# dd XXXXX XXXXX XXX XXXXX XXXXX XXXXX XX.X XXX mm/yy dd XXXXX XXXXX  $\mathbf{x}\mathbf{x}\mathbf{x}$ XXXXX xx.x XXXXX XXXXX XXX mm/yy dd XXXXX XXXXX XXXXX XXX XXXXX XX.X XXXXX XXX mm/yy dd XXXXX XXXXX XXXXX xxxxx $\mathbf{x}\mathbf{x}\mathbf{x}$ XXXXX XX.X  $\mathbf{x}\mathbf{x}\mathbf{x}$ dd mm/yy XXXXX XXXXX **XXXXX** XXXXX xxxXXXXX xx.x xxxdd mm/yy XXXXX XXXXX XXXXX xxxxx  $\mathbf{x}\mathbf{x}\mathbf{x}$ XXXXX xx.x xxxmm/yy dd XXXXX XXXXX xxxxx XXX XXXXX XXXXX xx.x xxx

Notes: Ordering based on "PK-TRF USAGE" for high days, "EVHD CCS/MS" for monthly EVHD's.

The "\*" flag indicates unreasonable ot outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The Peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 17 of 21) (8.07, 8.10)

CLLIcode

G.Issue

Company Id: nnn

DMS10 MF Receivers Traffic Machine Load and Service Summary Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy Officewide Values

High Days	:										
DATE	HOUR	PK-TRF USAGE	CCS /MF TRK	MF TRKS	DELAY	MFR CALLS	MFR PC	HT SEC	ovf %	AVG CCS /VOICE LOOP	T-L ML %
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxx	xx.x	xxxxx	xxxxx	xxxxx	xx:x	xxxxx	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	xx.x	xxxxx	xxxxx	xxxxx	xx.x	XXXXX	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	xx.x	XXXXX	xxxxx	XXXXX	xx.x	XXXXX	xx.x
mm/dd/yy*		XXXXX	XXXXX	XXX	xx.x		xxxxx			XXXXX	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	xx.x	xxxxx	xxxxx	XXXXX	xx.x	XXXXX	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	xx.x	XXXXX	xxxxx	XXXXX	xx.x	XXXXX	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	xx.x		xxxxx			xxxxx	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	xx.x		XXXXX			XXXXX	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	xx.x		xxxxx			XXXXX	xx.x
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxx	xx.x		xxxxx			XXXXX	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	xx.x		xxxxx			XXXXX	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	xx.x		XXXXX			XXXXX	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	xx.x		XXXXX			XXXXX	XX.X
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXX	XX.X		XXXXX			XXXXX	XX.X
mm/dd/yy	hh:mm	XXXXX	xxxxx	XXX	xx.x	XXXXX	xxxxx	XXXXX	XX.X	XXXXX	xx.x
Monthly E	VHD's:										
			EVHD		AD	P AD	P CCS	CURR			
		EVHD	CCS/MF	ADP	CCS		DICE	MF	CAP	CAP	
MONTH D	M	CCS	TRKS	ccs	TR		LOOP	TRKS	CCS	%	NCI
	-										
mm/yy d	d	xxxxx	xxxxx	xxxx	x xxx	xx x	xxxx	xxx	xxxxx	xx.x	xxxxx
mm/yy d	ld	xxxxx	xxxxx	XXXX	x xxx	xx x	xxxx	xxx	xxxxx	xx.x	xxxxx
mm/yy d	ld	xxxxx	XXXXX	XXXX	x xxx	xx x	xxxx	xxx	xxxxx	xx.x	xxxxx
OFFICE 3H	M	xxxxx	xxxxx	XXXX	x xxx	xx x	xxxx	xxx	xxxxx	xx.x	xxxxx
mm/yy d	ld	xxxxx	xxxxx	xxxx	x xxx	xx x	xxxx	xxx	xxxxx	xx.x	xxxx
mm/yy d	ld	xxxxx	XXXXX	XXXX	x xxx	XX X	XXXX	XXX	xxxxx	xx.x	xxxxx
. 2 2 "	ld	XXXXX	xxxxx	XXXX	x xxx	XX X	XXXX	XXX	xxxxx	xx.x	xxxxx
	ld	xxxxx	xxxxx	XXXX	x xxx	xx x	xxxx	xxx	xxxxx	xx.x	xxxxx
	ld	XXXXX	xxxxx	XXXX	x xxx	xx x	XXXX	XXX	xxxxx	xx.x	xxxxx
	ld	XXXXX	XXXXX	XXXX	x xxx	xx x	XXXX	XXX	xxxxx	xx.x	xxxxx
mm/yy d	ld	xxxxx	xxxxx	XXXX	x xxx	xx x	XXXX	XXX	xxxx	xx.x	xxxxx
	ld	XXXXX	XXXXX	XXXX	x xxx	xx x	xxxx	xxx	xxxxx	xx.x	xxxxx
mm/yy d	ld	xxxxx	xxxxx	XXXX	x xxx	xx x	xxxx	xxx	xxxxx	xx.x	xxxxx

Notes: Ordering based on "PK-TRF USAGE" for high days, "EVHD CCS/MS" for monthly EVHD's.

The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 18 of 21) (8.07, 8.10)

CLLIcode

G.Issue

Company Id: nnn

## DMS10 Analog Shelves Traffic Machine Load and Service Summary Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy Officewide Values

High Days	•	PK-TRF			PEG	CNT	нт	SEC		% ML	
DATE	HOUR	NTWK USAGE	CCS /AMS	CCS /ATRK	AMS	ATRK	AMS	ATRK	ORIG	INC	ANA
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xx.x	xx.x	xx.x
mm/dd/yy*	hh:mm	XXXXX	XXXXX	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xxxxx	xxxxx	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	XXXXX	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
1	1.1		********					** ** ** ** **	V . V	v v v	xx.x
mm/dd/yy	hh:mm	XXXXX	XXXXX	XXXXX	xxxxx	xxxxx	XXXXX	xxxxx	AA.A	AA . A	лл.л
		EVHD	EVHD	xxxxx	ES		EST	ADP	AI		ANA
				CURR		Γ		·		OP	
Monthly E	:VHD's:	EVHD NTWK CCS	EVHD		EST	Γ VE	EST SLAVE S/ATRK	ADP	AI CO	OP CS	ANA
mm/yy d	CVHD's:	EVHD NTWK	EVHD NTWK	CURR	EST SLA	T VE AMS CC	EST SLAVE	ADP CCS	AI C( /A:	DP CS FRK	ANA MUX
Monthly E  MONTH D   mm/yy d	CVHD's:	EVHD NTWK CCS	EVHD NTWK CCS/ELT	CURR ELT	EST SLAV CCS/A	T VE AMS CC  xx	EST SLAVE S/ATRK	ADP CCS /AMS	AI CC /AI 	OP CS CRK 1	ANA MUX LOOPS
Monthly E  MONTH D  mm/yy d  mm/yy d	CVHD's:	EVHD NTWK CCS  xxxxx xxxxx	EVHD NTWK CCS/ELT  xxxxx xxxxx xxxxx	CURR ELT  XXXX XXXX	EST SLAY CCS/A	T VE AMS CC  xx xx xx	EST SLAVE S/ATRK xxxxx xxxxx	ADP CCS /AMS  xxxxx xxxxx	AI CC /AT **** ***	OP CS FRK 1	ANA MUX LOOPS
MONTH D mm/yy d mm/yy d mm/yy d	WHD's:	EVHD NTWK CCS  xxxxx xxxxx	EVHD NTWK CCS/ELT  xxxxx xxxxx	CURR ELT  xxxx	EST SLAY CCS/A	T VE AMS CC xx xx xx	EST SLAVE S/ATRK xxxxx xxxx	ADP CCS /AMS  xxxxx xxxxx	AI CC /AI  XXX XXX	OP CS FRK 1	ANA MUX LOOPS
Monthly E  MONTH D   mm/yy d  mm/yy d  mm/yy d  OFFICE 3H	WHD's:	EVHD NTWK CCS  xxxx xxxx xxxx	EVHD NTWK CCS/ELT  xxxxx xxxxx xxxxx	CURR ELT  xxxx xxxx xxxx	EST SLAY CCS/A	T VE AMS CC xx xx xx xx	EST SLAVE S/ATRK xxxxx xxxxx	ADP CCS /AMS  xxxxx xxxxx xxxxx	AI CC /AT  xxx xxx xxx xxx	DP CS FRK 1 	ANA MUX LOOPS  XXXXX XXXXX
Monthly E  MONTH D   mm/yy d  mm/yy d  mm/yy d  OFFICE 3H	CVHD's:	EVHD NTWK CCS  xxxxx xxxxx xxxxx xxxxx xxxxx	EVHD NTWK CCS/ELT  xxxxx xxxxx xxxxx xxxxx xxxxx	CURR ELT  xxxx xxxx xxxx xxxx	EST SLAY CCS/A	T VE AMS CC xx xx xx xx	EST SLAVE S/ATRK xxxxx xxxxx xxxxx xxxxx	ADP CCS /AMS  xxxxx xxxxx xxxxx xxxxx	AI CC /AT  XXX XXX XXX  XXX	DP CS FRK 1 KXX 1 KXX 1 KXX 1	ANA MUX LOOPS xxxxx xxxxx xxxxx
Monthly E  MONTH D   mm/yy d  mm/yy d  orfice 3H  mm/yy d  mm/yy d	CVHD's:  OM  Id  Id  Id  Id  Id	EVHD NTWK CCS  xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	EVHD NTWK CCS/ELT  xxxxx xxxxx xxxxx xxxxx  xxxxx	CURR ELT  xxxx xxxx xxxx  xxxx	EST SLAY CCS/A	T VE AMS CC xx xx xx xx	EST SLAVE S/ATRK xxxxx xxxxx xxxxx xxxxx	ADP CCS /AMS  xxxxx xxxxx xxxxx xxxxx	AI CC /AT  XXX XXX XXX XXX XXX	DP CS FRK 1 KXX 1 KXX 1 KXX 1	ANA MUX LOOPS xxxxx xxxxx xxxxx xxxxx
Monthly E  MONTH D   mm/yy d  mm/yy d  OFFICE 3H  mm/yy d  mm/yy d  mm/yy d	CVHD's:	EVHD NTWK CCS  xxxxx xxxxx xxxxx xxxxx  xxxxx	EVHD NTWK CCS/ELT  xxxxx xxxxx xxxxx xxxxx  xxxxx	CURR ELT  xxxx xxxx xxxx  xxxx	EST SLAY CCS/A XXXX XXXX XXXX XXXX	T VE AMS CC xx xx xx xx xx xx	EST SLAVE S/ATRK xxxxx xxxxx xxxxx xxxxx xxxxx	ADP CCS /AMS  xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx	AI CC /AT XXX XXX XXX XXX XXX XXX XXX	DP CS FRK 1 KXX 1 KXX 1 KXX 1 KXX 1	ANA MUX LOOPS xxxxx xxxxx xxxxx xxxxx
MONTH D	CVHD's:  OM  Id  Id  Id  Id  Id	EVHD NTWK CCS  xxxxx xxxxx xxxxx xxxxx  xxxxx	EVHD NTWK CCS/ELT  xxxxx xxxxx xxxxx  xxxxx xxxxx xxxxx xxxxx	CURR ELT xxxx xxxx xxxx xxxx xxxx	EST SLAY CCS/A	T VE AMS CC xx xx xx xx xx xx xx	EST SLAVE S/ATRK xxxxx xxxxx xxxx xxxx xxxx xxxx	ADP CCS /AMS  xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	AI CC /A1	DP CS FRK 1  KXX 1 KXX 1 KXX 1 KXX 1 KXX 1 KXX 1 KXX 1	ANA MUX LOOPS xxxxx xxxxx xxxxx xxxxx xxxxx
Monthly E  MONTH D   mm/yy d  mm/yy d  OFFICE 3H  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d	CVHD's:	EVHD NTWK CCS  xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	EVHD NTWK CCS/ELT  xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	CURR ELT xxxx xxxx xxxx xxxx xxxx xxxx	EST SLAY CCS/A CCS	T VE AMS CC xx xx xx xx xx xx xx xx	EST SLAVE S/ATRK xxxxx xxxxx xxxx xxxx xxxx xxxx	ADP CCS /AMS  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	AI CC /A1	DP CS FRK  KXX KXX KXX KXX KXX KXX KXX	ANA MUX LOOPS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx
MONTH D mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d mm/yy d	EVHD's:  OM  Id  Id  Id  Id  Id  Id  Id  Id  Id  I	EVHD NTWK CCS  xxxxx xxxxx xxxxx  xxxxx xxxxx xxxxx xxxx xxxxx xxxxx xxxx	EVHD NTWK CCS/ELT xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	CURR ELT xxxx xxxx xxxx xxxx xxxx xxxx xxx	EST SLAY CCS/// XXXX XXXX XXXX XXXX XXXX XXXX	T VE AMS CC xx xx xx xx xx xx xx xx xx xx	EST SLAVE S/ATRK xxxxx xxxxx xxxx xxxx xxxx xxxx	ADP CCS /AMS  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	AI CC /AT  XX3 XX3 XX3 XX3 XX3 XX3 XX3 XX3 XX	DP CS FRK  KXX KXX KXX KXX KXX KXX KXX KXX	ANA MUX LOOPS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx
Monthly E  MONTH D   mm/yy d  mm/yy d  OFFICE 3H  mm/yy# d  mm/yy# d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d  mm/yy d	EVHD's:  OM  Id  Id  Id  Id  Id  Id  Id  Id  Id  I	EVHD NTWK CCS  xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	EVHD NTWK CCS/ELT xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx	CURR ELT XXXX XXXX XXXX XXXX XXXX XXXX XXX	EST SLAY CCS/// XXXX XXXX XXXX XXXX XXXX XXXX	I VE AMS CC  xx xx xx xx  xx xx xx xx xx xx xx	EST SLAVE S/ATRK xxxxx xxxxx xxxx xxxx xxxx xxxx	ADP CCS /AMS  XXXXX XXXXX XXXXX XXXXX XXXXX XXXXX XXXX	AI CC /AT  XX3 XX3 XX3 XX3 XX3 XX3 XX3 XX3 XX	DP CS FRK  ***** **** **** **** **** **** **	ANA MUX LOOPS xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxx

Notes: Ordering based on "PK-TRF NTWK USAGE" for high days, "EVHD NTWK CCS/ELT" for monthly EVHD's.

The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 19 of 21) (8.07, 8.10)

CLLIcode

G.Issue

Company Id: nnn

DMS10 Digital Shelves
Traffic Machine Load and Service Summary
Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy
Officewide Values

High Days:		PK-TRF			PEG	CNT	нт	SEC		% ML	
DATE	HOUR	NTWK USAGE	CCS /DMS	CCS /DTRK	DMS	DTRK	DMS	DTRK	INC	ORIG	DIG
mm/dd/yy h		xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
	4	xxxxx	xxxxx	xxxxx	xxxxx		xxxxx	xxxxx	xx.x	xx.x	xx.x
		XXXXX	xxxxx		xxxxx		XXXXX			xx.x	
mm/dd/yy h	nh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy* h	nh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/vy h	nh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy h	nh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy h	ռի: տտ	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy ł	ոհ:տտ	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy h	nh:mm	XXXXX	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy h	nh:mm	xxxxx	xxxxx	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy h	nh:mm	XXXXX	XXXXX	XXXXX	xxxxx	xxxxx	XXXXX	XXXXX	xx.x	xx.x	xx.x
mm/dd/yy h	nh:mm	XXXXX	XXXXX	XXXXX	xxxxx	XXXXX	XXXXX	XXXXX	xx.x	xx.x	xx.x
mm/dd/yy i	hh:mm	XXXXX	XXXXX	XXXXX	xxxxx	xxxxx	XXXXX	XXXXX	xx.x	xx.x	xx.x
mm/dd/yy h	hh:mm	XXXXX	XXXXX	xxxxx	xxxxx	xxxxx	XXXXX	xxxxx	xx.x	xx.x	xx.x
Monthly EV	HD's:										
•		CHV	EVHD		ES?	Γ	EST	ADP	Al	OP	DIG
	N	ITWK	NTWK	CURR	SLA	VE.	SLAVE	CCS	C	CS	MUX
MONTH DM	C	cs c	CS/ELT	ELT	CCS/I	OMS C	CS/DTRK	/DMS	\D.	ΓRK	LOOPS
	-										
mm/yy dd	x	XXXX	xxxxx	xxxx	XXX	ХX	XXXXX	XXXXX	XX:	XXX	XXXXX
mm/yy dd	х	XXXX	XXXXX	XXXX	XXX	ХX	XXXXX	XXXXX	XX	XXX	xxxxx
mm/yy dd	x	XXXX	XXXXX	XXXX	XXX	ХX	XXXXX	xxxxx	XX	XXX	XXXXX
OFFICE 3HM		xxxx	xxxxx	xxxx	xxx		xxxxx	xxxxx		xxx	xxxxx
mm/yy dd	х	xxxx	xxxxx	xxxx	xxx	хx	xxxxx	xxxxx	xx	xxx	xxxxx
mm/yy# dd	X	XXXX	XXXXX	XXXX	XXX	XX	XXXXX	XXXXX	XX	XXX	xxxxx
mm/yy dd	Х	XXXX	XXXXX	xxxx	XXX	ХX	XXXXX	xxxxx	XX	xxx	xxxxx
mm/yy dd	Х	XXXX	xxxxx	xxxx	XXX	ХX	XXXXX	xxxxx	XX	xxx	xxxxx
mm/yy dd	X	XXXX	xxxxx	xxxx	XXX	ХX	XXXXX	xxxxx	XX	xxx	xxxxx
mm/yy dd	х	XXXX	xxxxx	xxxx	XXX	хx	XXXXX	xxxxx	XX	xxx	xxxxx
mm/yy dd	х	XXXX	xxxxx	xxxx	XXX	ХX	XXXXX	xxxxx	XX	xxx	xxxxx
mm/yy# dd	X	XXXX	xxxxx	xxxx	XXX	ХX	XXXXX	xxxxx	XX	XXX	xxxxx
mm/yy dd	Х	XXXX	xxxxx	xxxx	XXX	хх	XXXXX	xxxxx	XX	xxx	xxxxx

Notes: Ordering based on "PK-TRF NTWK USAGE" for high days, "EVHD NTWK CCS/ELT" for monthly EVHD's.

The "\*" flag indicates unreasonable or outlier data.

The "#" flag marks a month with less than 15 unflagged days of data.

The peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 20 of 21) (8.07, 8.10)

CLLIcode

G.Issue

Company Id: nnn

DMS10 Processor -- Occupancy and Delay Peak Half-Hourly Data Traffic Machine Load and Service Summary Data Year Ending mm/dd/yyyy Data Reported Through mm/dd/yyyy Officewide Values

		PEAK	O . T				CAI			<b>%</b>		ľ
DATE	HOUR	CPU %OCC	O+I CALLS	DP	DGT	TRK MF	DP	DGT	MF	DP		MF
mm/dd/yy	hh:mm	xx.x	xxxxx		xxxx	xxxx	xxxxx	xxxxx		xx.x	xx.x	xx.x
mm/dd/yy*	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy*	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x
mm/dd/yy	hh:mm	xx.x	xxxxx	xxxx	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xx.x	xx.x	xx.x

Monthly EVHD's:	Mon	thlv	EVHD'	s	:
-----------------	-----	------	-------	---	---

nonchi	LVIIL		E1111D			EUIID	EVHD C	PU USAG	E (ms) per
MONTH	DM	AVG CPU %OCC	EVHD CPU %OCC	CURR MS	CURR ELT	EVHD O+I CALLS	CURR MS	CURR ELT	EVHD O+I CALLS
mm/yy mm/yy	dd dd	 xx.x xx.x	xxx.x xxx.x	xxxx	xxxx	xxxxx	xxxxx	xxxxx	XXXXX
mm/yy	dd	xx.x	xxx.x	****	****	*****	*****	****	*****
OFFICE	ЗНМ	xx.x	xxx.x	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xxxxx
mm/yy	dd	xx.x	xxx.x	xxxx	XXXX	xxxxx	XXXXX	xxxxx	xxxxx
mm/yy#	dd	xx.x	xxx.x	XXXX	XXXX	xxxxx	XXXXX	xxxxx	xxxxx
mm/yy	dd	xx.x	xxx.x	XXXX	XXXX	xxxxx	xxxxx	XXXXX	XXXXX
mm/yy	dd	xx.x	xxx.x	XXXX	XXXX	XXXXX	XXXXX	XXXXX	xxxxx
mm/yy	dd	xx.x	xxx.x	XXXX	XXXX	XXXXX	xxxxx	XXXXX	XXXXX
mm/yy	dd	xx.x	xxx.x	xxxx	XXXX	xxxxx	xxxxx	XXXXX	XXXXX
mm/yy	dd	xx.x	xxx.x	XXXX	XXXX	XXXXX	xxxxx	XXXXX	XXXXX
mm/yy	dd	xx.x	xxx.x	XXXX	xxxx	xxxxx	xxxxx	XXXXX	xxxxx
mm/yy	dd	xx.x	xxx.x	xxxx	xxxx	xxxxx	xxxxx	xxxxx	xxxxx

Notes: Ordering based on "PEAK CPU % OCC" for high days,
"EVHD CPU USAGE per CURR MS" for monthly EVHD's.

The "\*" flag indicates unreasonable and outlier data.

The "#" flag marks a month with less than 15 unflagged days of data. The peak value column is underlined double ("===").

Fig. 14—COER Output (Sheet 21 of 21) (8.07, 8.10)

## ORIGINATING PEG COUNT RELIABILITY COMPARISONS

1. TOTAL ORIGI	NATING CALLS ≤ DIA	AL TONE PEG COUNT
OPMOO2 Totc	OPMOO5 DIAL	
	<b>\$</b>	
		·
2. DIGITONE CA	LLS 🕏 DIGITONE REC	CEIVER PEG
OPMOO2 DGTC	OPMO05 DGTR	
	<b>=</b>	
3. ORIGINATING + REVERTING STARTS.	TERMINATING + ORIG > TOTAL CALLS - PE	GINATING OUTGOING + ORIGINATING NONCOMPLETING ERMANENT SIGNAL - PARTIAL DIAL ABANDON - FALSE
0PM001		OPM002
ORTM	_	TOTC
+		-
OROG	_	PSIG
+		-
ORNC	_	PABN
+		_
RVRT	_	FSTR
=	] <b>&gt;</b>	=

Fig. 15—Data Reliability Comparison Worksheet (Sheet 1 of 3) (9.10)

OUTGUING CA	ALL PEG COUNT RE	TIABILITY COMPAR	!ISONS		
	ING OUTGOING ≲ ≲ DIGIT SENDER		TRUNK GROU	PS - INCOMINO	3
OPM001	0PM004	0PM005			
OROG	S OGP	DSND			
+					
INOG	_				
=					
	<b>=</b>	<b>=</b>			
SERVI	CE CIRCUIT PEG C	OUNT COMPARISON	S		
1. SERVICE ;	≲ SUM OF INDIVI	DUAL SERVICE CIR	CUITS & S	UM OF SERVICE	NETWORK
OPM005	0PM005	0PM006			
SNET	DSDN BUSY + RNGB + RORD + DIAL + HOWL + LOW + CWT + SPDT + CFMT +				
1 1	× =	¬	7		

Fig. 15—Data Reliability Comparison Worksheet (Sheet 2 of 3) (9.10)

## INCOMING PEG COUNT RELIABILITY COMPARISONS

1.	MF RECEIVER CAL	.LS 💢 MF RECEI	IVER # SUM OF MF INCOMING TRUNKS GROUPS.
	OPMOO3 MFRC	OPMOO5 MFR	OPMOO4 Σ MF IGP
	<u> </u>		<b>≈</b> □
2.			ING OUTGOING + INCOMING NONCOMPLETING ☆ TOTAL INCOMING ☆ SUM OF INCOMING TRUNK GROUPS - PARTIAL ABANDON
	OPM001	OPM003	OPM004
	INTM	TOTC	Σ IGP
	•	-	-
	INOG	PABN	_ OPMOO3 Pabn

=

Fig. 15—Data Reliability Comparison Worksheet (Sheet 3 of 3) (9.10)

INNC